

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 South Market, Room 2078
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R. 82-3-117

API NUMBER 15-033-21034-0000 ^{KCC} ^{ab} ⁵²⁴⁷⁶

LEASE NAME Griffith Farms

WELL NUMBER 30-2

160 Ft. from N Section Line

1950 Ft. from E Section Line

SEC 30 TWP 32S RGE 18 West

COUNTY Comanche

Date Well Completed 12/15/1999

Plugging Commenced 3/30/2004

Plugging Completed 3/31/2004

TYPE OR PRINT
NOTICE: Fill out **completely**
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Samuel Gary Jr. & Associates, Inc.

ADDRESS 1670 Broadway, Suite 3300 Denver, CO 80202-4838

PHONE # (303) 831-4673 OPERATORS LICENSE NO. 3882

Character of Well Gas

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 3/24/2004 (date)

by Steve Durrant (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing Formation _____ Depth to Top 4860' Bottom 5700' T.D. 6125'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
		0'	43'	20"	43'	0'
		0'	666'	8-5/8"	666'	0'
		0'	5882'	5-1/2"	5882'	2004'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set.

Set CIBP @ 4800' & capped w/ 2 sx cmt. Shot 5-1/2" csg @ 2004' & pulled to 1200'. Filled csg w/ 15 sx gel wtr & spotted 50 sx @ 1200'. Pulled csg to 680'. Spotted 50 sx @ 680'. Pulled csg to 400'. Spotted 30 sx @ 400'. Pulled all csg & topped off w/ 10 sx. Plugged w/ 15 sx gel & 150 sx 60-40 poz w/ 6% gel. Plugging complete @ 4:30 pm, 3-31-04.

State man on loc - Steve Middleton.

(if additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Wild West Well Service, Inc. License No. 32592

Address P.O. Box 433 Ness City, KS 67560-0433

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Samuel Gary Jr. & Associates, Inc.

STATE OF KANSAS COUNTY OF BARTON, ss.

Thomas Larson, Consultant

(Employee of Operator) or Operator of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Thomas Larson

(Address) 562 W. State Road 4, Olmitz, KS 67564

SUBSCRIBED AND SWORN TO before me this 17th day of June, 2004

Carol S. Larson

Carol S. Larson

Notary Public

My Commission Expires: June 25, 2005



Form CP-4
Revised 05-88

RECEIVED
JUN 18 2004

KCC WICHITA