

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bittling Building  
Wichita, Kansas

WELL PLUGGING RECORD

Rooks

County, Sec. 19 Twp. 8 Rge. 17 (E) W (W)

Location as "NE/CNW/SW" or footage from lines SE/4 SW/4 NE/4

Lease Owner V.D. Sidey Oil Company

Lease Name V.D. Sidey Oil Co-Stamper Well No. 2.

Office Address Russell, Kansas.

Character of Well (completed as Oil, Gas or Dry Hole)

Date well completed 19

Application for plugging filed 19

Application for plugging approved 19

Plugging commenced September 1 19 55

Plugging completed September 3 19 55

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes.

Name of Conservation Agent who supervised plugging of this well Eldon Petty

Producing formation Depth to top Bottom Total Depth of Well 3404 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from 3404 feet to surface feet for each plug set.

Hole had been plugged back with cement plug and sand to 3281 ft; Pipe filled with sand from 3281 to 3100 ft. Four sacks of cement placed in hole with bailer to form cement plug from 3100 to 3068 feet; Casing shot off at 2887 feet, and after pipe pulled, Halliburton pump trucks pumped twenty sacks of mud and seventy sacks of cement into hole under pressure. Plugging Complete, with cement reaching to top of hole.

RECEIVED  
STATE CORPORATION COMMISSION

Name of Plugging Contractor Barnes and Sons Pipe Pulling Co  
Address Russell, Kansas.

Sep 15, 1955  
CONSERVATION DIVISION  
WICHITA, KANSAS

STATE OF Kansas, COUNTY OF Russell, ss.

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) V.D. Sidey  
Box 387 Russell, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 14<sup>th</sup> day of September, 1955

My commission expires September 17, 1956  
Marquette Byrne Notary Public.

PLUGGING  
FILE SEC 19 T 8 R 170  
BOOK PAGE 147 LINE 15

15-163-02715-00-00

# SIDEY DRILLING CO.

BUILDING & LOAN BLDG. P. O. BOX 387  
RUSSELL, KANSAS

Company V. D. Sidey Oil Company

Sec. 19 T. 8 R. 17

Farm Stamper

No. 2

Loc. SE SW NE

Total Depth 3395'

Comm. 2-27-55

Comp. 3-9-55

County Rocks

Shot or Treated

Contractor Sidey Drilling Company

Issued

### Casing

20	10	
15½	8¼	103'
12½	6%	
13%	5 5/16	3395'

Elevation 1970 KB  
1968 DF

Production

Figures Indicate Bottom of Formations

0-45	Shale & Shells	1915-2035	Lime & shale
45-50	Sand	2035-2075	Lime
50-102	Shale & Shells	2075-2180	Lime & Shale
102-225	Shale & Shells	2180-2365	Lime & Shale
225-525	Shale & Shells	2365-2500	Lime & Shale
525-595	Sand & Shale	2500-2590	Lime & Shale
595-605	Sand	2590-2740	Lime & Shale
605-670	Shale & Shells	2740-2895	Lime & Shale
670-700	Sand	2895-3000	Lime & Shale
700-825	Shale & Shells	3000-3060	Lime & Shale
825-1010	Sand	3060-3140	Lime & Shale
1010-1085	Red Bed	3140-3195	Lime & Shale
1085-1303	Red Bed	3195-3240	Lime
1303-1335	Anhydrite	3240-3305	Lime
1335-1420	Shale & Shells	3305-3350	Lime
1420-1760	Shale & Shells	3350-3395	Lime & Shale TD
1760-1820	Shale & Shells		
1820-1915	Lime & Shale		

STATE OF KANSAS, COUNTY OF RUSSELL) ss.

I, V. D. Sidey, of the Sidey Drilling Company, upon oath state that the above and foregoing is a true and correct copy of the log on the Stamper #2.

V. D. Sidey  
V. D. SIDEY

Subscribed and sworn to before me this 14<sup>th</sup> day of September 1955

My Commission Expires: Sept. 17, 1956

Marguerite Byrne  
NOTARY PUBLIC

RECEIVED  
STATE COMMISSION  
SEP 15 1955  
CONSERVATION DIVISION  
Wichita, Kansas

PLUGGING  
PLX SEC 19 T 8 R 17W  
BOOK PAGE 147 LINE 15