

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

Rooks County. Sec. 19 Twp. 8 Rge. 17W (E) (W)

Location as "NE/CNW/SW" or footage from lines SE SE SW

Lease Owner D. G. Hansen

Lease Name Krug Well No. 1

Office Address Logan, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed December 16 19 57

Application for plugging filed December 16 19 57

Application for plugging approved December 16 19 57

Plugging commenced December 16 19 57

Plugging completed December 16 19 57

Reason for abandonment of well or producing formation Lost joint of surface casing in hole; unable to get back on bottom.

If a producing well is abandoned, date of last production \_\_\_\_\_ 19 \_\_\_\_\_

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty, Hays, Kansas

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3135 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	176.46'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled hole with heavy mud to 550'. Set plug. Put in 20 sacks cement. Filled to 150'. Set plug. Put in 1/2 sack hulls and 15 sacks cement. Filled with heavy mud up to 40'. Set plug. Filled to top with 1/2 sack hulls and 10 sacks cement.

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 21 1957  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor C-G Drilling Co.  
Address 107 Rule Bldg., Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
G. F. Galloway (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) G. F. Galloway  
107 Rule Bldg.  
(Address)

SUBSCRIBED AND SWORN TO before me this 20th day of December, 1957

My commission expires May 20, 1959  
Vicky Jacobs Notary Public.

PLUGGING  
FILE SEC 19 T 8 R 17W  
BOOK PAGE 40 LINE 34

CONTRACTOR'S WELL LOG

OPERATOR D. G. Hansen WELL NAME Krug #1  
 LOCATION SE SE SW SEC. 19-8-17 RIG NO. 1  
 COUNTY Rooks STATE Kansas  
 COMMENCEMENT DATE December 9, 1957 COMPLETION DATE December 16, 1957

LOG OF WELL

Elevation 1963' rotary bushing.  
 All measurements taken from the top of rotary bushing.

FROM	TO	FORMATION	DEVIATION FROM VERTICAL	REMARKS:
0	176	Shale		
176	475	Shale		
475	620	Sand		
620	840	Sand-Shale		
840	975	Sand		
975	1280	Red Bed		
1280	1315	Anhydrite		
1315	1455	Lime-Shale		
1455	1930	Lime-Shale		
1930	2130	Lime-Shale		
2130	2235	Lime-Shale		
2235	2425	Lime-Shale		
2425	2570	Lime-Shale	0° - 2500	
2570	2810	Lime-Shale	0° - 2750	
2810	2896	Lime-Shale		
2896	2975	Lime-Shale		
2975	3060	Lime-Shale	0° - 3000	
3060	3108	Lime-Shale		
3108	3128	Lime-Shale		DST 3080-3108'
3128	3135	Lime-Shale		DST 3104-3135'

CASING LEFT IN HOLE AFTER COMPLETION

Ran 176.46' (9 jts.) 8-5/8" OD Surface Casing.

STATE OF KANSAS }  
 COUNTY OF SEDGWICK } ss.

**RECEIVED**  
 STATE CORPORATION COMMISSION  
 Dec 21, 1957  
 DEC 21 1957

CONSERVATION DIVISION  
 W. H. C. Kansas

The undersigned hereby certifies that to the best of his knowledge and belief, the above facts are true and correct.

C-G DRILLING CO.

By G. F. Galloway  
 G. F. Galloway

SUBSCRIBED AND SWORN TO BEFORE ME THIS 20th day of December, 1957.

Vicky Jacobs  
 Vicky Jacobs, Notary Public

My commission expires: May 20, 1959

PLUGGING  
 WELL SEC 19 T. 8 R. 14W  
 BOOK PAGE 70 LINE 34