

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-035-23893-00-00
Spot: SESWNE Sec/Twnshp/Rge: 9-34S-8E
3017 feet from S Section Line, 1702 feet from E Section Line
Lease Name: ZIMMERMAN Well #: 2
County: COWLEY Total Vertical Depth: 2430 feet

Operator License No.: 5205
Op Name: MID-CONTINENT ENERGY CORP.
Address: 105 S. BROADWAY, STE 360
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	2429		145 SX
SURF	8.625	137		120 SX

\$ 78.98

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/10/2006 9:00 AM
Plug Co. License No.: 32884 Plug Co. Name: ELMORE'S, INC.
Proposal Rcvd. from: JOHN ELMORE Company: ELMORE'S, INC. Phone: (620) 725-5538

Proposed Plugging Method: See actual report.

Plugging Proposal Received By: DUANE KRUEGER WitnessType: PARTIAL
Date/Time Plugging Completed: 04/11/2006 2:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

4/10/2006 -- RIH with 1" at 1913'. Elmore's mixed and pumped 10 bbls gel flush with 10 sacks of class A cement. Tagged cement at 1775'.
4/11/2006 -- RIH with 1" on backside of 4-1/2" at 28'. Pumped with cement. RIH with 1" at 500'. Elmore's mixed and pumped 65 sacks of 60/40 posmix with 4% gel to surface.
Tagged solid on backside 4-1/2" at 28'.
Elmore's #6453

Perfs:

Top	Bot	Thru	Comments
2016	2021		
1913	1918		

**RECEIVED
KCC DISTRICT #2
MAY - 9 2006
WICHITA, KS**

**RECEIVED
MAY 22 2006
KCC WICHITA**

Remarks:

Plugged through: TBG

District: 02

Signed

Duane R. Krueger
(TECHNICIAN)

INVOICED

DATE 5-23-06
2006061685

Form CP-2/3

PKT