

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-147-30115-00-00  
Spot: SESE Sec/Twnshp/Rge: 20-4S-18W  
660 feet from S Section Line, 660 feet from E Section Line  
Lease Name: ELSIE Well #: 4  
County: PHILLIPS Total Vertical Depth: 3360 feet

Operator License No.: 5252  
Op Name: NIXON, R P OPERATIONS, INC  
Address: 207 W 12TH  
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	3333	0	w/unknown sxs cmt
SURF	8.625	215	0	w/140 sxs cmt

*H 109.20*

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/16/2006 9:00 AM  
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC  
Proposal Rcvd. from: DUANE ACTERBURY Company: NIXON, R P OPERATIONS, INC. Phone: (785) 628-3834

Proposed Plugging Method: Ordered out 225 sxs 60/40 pozmix - 10% gel - 400# hulls.  
Well squeezed at 2900' w/75 sxs. 1450' w/175 sxs and 741'.

Plugging Proposal Received By: JAY PFEIFER Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 05/16/2006 12:00 PM KCC Agent: JAY PFEIFER

Actual Plugging Report:

Perfs:

Well sanded back to 2918'.  
TIH with tubing to 2902' - mixed and circulated cement with 145 sxs.  
POOH. Topped with 75 sxs cement. S.I.P. 500#.  
Hooked up to the annulus - Instant 400#.

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed

*Jay Pfeifer*

(TECHNICIAN)

INVOICED

DATE

5-23-06

TEL. NO.

200 606 11087

RECEIVED

MAY 22 2006


KCC WICHITA

Form CP-2/3

MAY 17 2006

*PKI*

4-3 Map No.  
OPER T.W. JACKSON - PHILLIPSBURG, KS.



S-T-R 20-4S-18W  
SPOT C SE SE  
CO PHILLIPS (KS)  
ELEV 1906 KB

WELL #4 ELSIE  
CONTR RED TIGER  
FIELD STONEMAN (LAN OIL)  
I.P. P 81 BOPD (GR 35.5) + 24% WTR, LAN 3097-  
3270 (OA)

(KB LOG)

ANH 1426 + 480  
TOP 2854 - 948  
HB 3053 - 1147  
TOR 3078 - 1172  
LAN 3096 - 1190  
BKC 3322 - 1416  
LTD 3358 - 1452  
RTD 3360 - 1454

GEOL. - RAY GOODIN  
SPUD 1-12-66 8" 215 W/140 SX.

DST #1 (LAN) 3155-3205, OP 1 HRS, 120' GIP, R 40' HOCM  
W/SHO CLEAN OIL, ISIP 655#/30", FP'S 12-22#, FSIP  
586#/30"

DST #2 (LAN) 3240-80, OP 1 HR, R 110' GCM VERY SLI OC,  
ISIP 517#/30", FP'S 26-69#, FSIP 500#/30"

RTD 3360, RAN LOG, 4" 3333 W/250 SX.

MICT, PF LANS FOR LIMITED ENTRY ACID TREATMENT

PF 1 SHOT PER FOOT @3269, 3229, 3196, 3157, 3099 (LAN),  
NTN, 500 MA & 10,000 RET A, RE PF 8/3268-70, 8/3228-30,  
16/3194-98, 8/3156-58, 16/3097-3101 (LAN), 8 PART LD W/  
GSO, POP

STATE POT: (4-1-66) P 81 BOPD ( GR 35.5 ) + 24% WTR, LAN  
3097-3270 (OA) - COMPLETED

Data Inc

JACKSON