

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-015-19338-00-00  
Spot: SENWNW Sec/Twnshp/Rge: 4-26S-4E  
4337 feet from S Section Line, 4481 feet from E Section Line  
Lease Name: RICE Well #: 1  
County: BUTLER Total Vertical Depth: 2655 feet

Operator License No.: 21878 • *6407 KCCS/23/06 PKT per CP215P4*  
Op Name: SNYDER, JIM *Flowers Production Company*  
Address: PO BOX 66  
HAMILTON, KS 66853

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	7	2450		
SURF	8.625	80		

*\$ 86.29*  
*Per Jim Snyder is responsible 4 Fees.*

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 02/28/2006 10:00 AM  
Plug Co. License No.: 32147 Plug Co. Name: K.E. SNYDER CO., LLC  
Proposal Rcvd. from: JOEL SNYDER Company: K.E. SNYDER CO., LLC Phone: (620) 344-6083

Proposed Plugging Method: See actual report.

Plugging Proposal Received By: DUANE KRUEGER WitnessType: PARTIAL  
Date/Time Plugging Completed: 03/10/2006 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

3/1/2006 -- Sanded well back 50' above perforations at 2350'. Dump bailed 12 sacks of cement on top. Cement top at 2300'. Shot 7" casing at 731'.  
3/3/2006 -- POOH with 731' of 7" casing and 80' of 8-5/8" casing.  
3/7/2006 -- RIH with tubing at 250'. Snyder mixed and pumped 145 sacks of 60/40 posmix with 4% gel. Tagged at 160'.  
3/10/2006 -- RIH with tubing at 155'. Snyder mixed and pumped 225 sacks of 60/40 posmix with 4% gel to surface. RIH with 1 joint 7" to mark hole.  
Snyder #06-003

Perfs:

RECEIVED  
KCC DISTRICT #2  
MAY - 9 2006  
WICHITA, KS

RECEIVED  
MAY 22 2006  
KCC WICHITA

Remarks:  
Plugged through: TBG

District: 02

Signed Duane R. Krueger  
(TECHNICIAN)

INVOICED  
DATE 5-23-06  
INV. NO. 2006061688

PKT