

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-015-19340-00-00  
Spot: SESWNW Sec/Twnshp/Rge: 4-26S-4E  
3011 feet from S Section Line, 4620 feet from E Section Line  
Lease Name: RICE Well #: 4  
County: BUTLER Total Vertical Depth: 2473 feet

Operator License No.: 6407 per CP-4  
31878 KCC 5/23/06  
PKT

Op Name: SNYDER, JIM Flowers Production Co Inc.  
Address: PO BOX 66  
HAMILTON, KS 66853 Per Jim Snyder is resp for Fees.  
String Size Depth (ft) Pulled (ft) Comment  
PROD 5.5 2425  
SURF 8.625 200 \$ 80.31

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/14/2006 10:00 AM  
Plug Co. License No.: 32147 Plug Co. Name: K.E. SNYDER CO., LLC  
Proposal Rcvd. from: JOEL SNYDER Company: K.E. SNYDER CO., LLC Phone: (620) 344-6083

Proposed Plugging Method: See actual report.

Plugging Proposal Received By: DUANE KRUEGER Witness Type: PARTIAL  
Date/Time Plugging Completed: 03/17/2006 4:30 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

3/14/2006 -- Sanded back at 2240'. Dumped bailed 7 sacks of cement on top.  
3/15/2006 -- Shot 5-1/2" casing at 709'. POOH with 709' of 5-1/2" casing.  
3/17/2006 -- RIH with tubing at 250'. Snyder mixed and pumped 105 sacks of 60/40 posmix with 4% gel to surface.  
Snyder #06-004

Perfs:  
**RECEIVED  
KCC DISTRICT #2  
MAY - 9 2006  
WICHITA, KS**

**RECEIVED  
MAY 22 2006  
KCC WICHITA**

Remarks:  
Plugged through: TBG

District: 02 Signed Duane R. Krueger  
(TECHNICIAN)

**RECEIVED**  
DATE 5-23-06  
2006061688

PKT