

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-135-23072-00-00
Spot: SESENW Sec/Twnshp/Rge: 28-16S-21W
2970 feet from S Section Line, 2970 feet from E Section Line
Lease Name: HILTABIDLE Well #: A-2
County: NESS Total Vertical Depth: 4250 feet

Operator License No.: 5399
Op Name: AMERICAN ENERGIES CORPORATION
Address: 155 N. MARKET, STE 710
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
DVT		1374		WITH 350 SX CMT
PROD	4.5	4249	0	WITH 500 SX CMT
SURF	8.625	327		WITH 125 SX CMT

\$ 138.13

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/01/2006 12:30 PM
Plug Co. License No.: 5399 Plug Co. Name: AMERICAN ENERGIES CORPORATION
Proposal Rcvd. from: THAD Company: AMERICAN ENERGIES CORPORAT Phone: (316) 263-5785

Proposed Plugging Method: RUN TUBING TO 4096' & PUMP 25 SX CMT & 300# HULLS. PULL TUBING TO 1300' & PRESSURE TEST CASING. PUMP CMT. PULL TUBING & TOP OFF. CHECK BACKSIDE.

Plugging Proposal Received By: STEVE DURRANT WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 05/01/2006 4:00 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

RUN TUBING TO 4096' & PUMPED 25 SX & 300# HULLS. PULLED TUBING TO 1300'. PRESSURED CASING TO 500# & HELD. PUMPED 120 SX CMT. CMT CIRCULATED. PULLED TUBING & TOPPED OFF WITH 40 SX CMT. TIED ONTO BACKSIDE AND PUMPED 1/4 BBL. PRESSURED TO 500# & HELD.

Perfs:


Top	Bot	Thru	Comments
4202	4206		

INVOICED
DATE 5-24-06
INV. NO. 200606061694

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED.

Plugged through: CSG

District: 01



Signed Michael Maier
(TECHNICIAN)

RECEIVED
MAY 24 2006
KCC WICHITA

[Handwritten signature]