

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-21175-00-00
Spot: SWSESE Sec/Twnshp/Rge: 4-17S-12W
330 feet from S Section Line, 990 feet from E Section Line
Lease Name: WONDRA Well #: 1
County: BARTON Total Vertical Depth: 3338 feet

Operator License No.: 4058
Op Name: AMERICAN WARRIOR, INC.
Address: PO BOX 399
GARDEN CITY, KS 67846

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	3332	0	100 SX
SURF	8.625	215	0	150 SX

105.49

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/18/2006 1:00 PM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Rcvd. from: KEVIN WILES, SR. Company: AMERICAN WARRIOR, INC. Phone: (620) 275-2963

Proposed
Plugging
Method:

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 05/18/2006 3:30 PM KCC Agent: CASE MORRIS

Actual Plugging Report:

Perforated at 380' - 775' - 1450'.
Ran tubing to 2000'.
Pumped 75 sxs 60/40 pozmix - 10% gel cement with 300# hulls.
Pulled to 1000'.
Circulated with 60 sxs cement with 200# hulls.
POOH. Pumped 60 sxs cement down casing.
Max. P.S.I. 300#. S.I.P. 200#.
Pumped 25 sxs into backside.
Max. P.S.I. 300#. S.I.P. 200#.

Perfs:

Top	Bot	Thru	Comments
3330	3332		

INVOICED

DATE 5-24-06
2006061695

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

HD

Signed Case Morris
(TECHNICIAN)

RECEIVED
MAY 24 2006
KCC WICHITA

Form CP-2/3

MAY 22 2006

ACT

137

PETROLEUM ENERGY, INC.
710 120 BLDG., WICHITA, KS.

4-17-12W
SW SE SE

#1 WONDRA

CONTR R & N DRILG. CO. CTY BARTON

GEOL _____ FIELD ODIN

E 1875 KB CM 7/5/77 CARD ISSUED 8/18/77 P 72 BOPD N/W
ARB 3332-38

+	+	+
+	+	+
+	+	+

API 15-29-21,175

SMP	TOPS	DEPTH	DATUM
HEEB		2869	- 944
TOR		2886	-1011
DDIG		2897	-1022
BR LM		3061	-1186
LANS		3078	-1203
ARR		3329	-1454
RTD		3338	-1463

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS

8-5/8" 215/150sx, 4 1/2" 3332/100sx
NO LOG
DST (1) 3064-85/30-30-30-30, 20' OCM,
SIP 43-43# FP 21-32# 32-32#
DST (2) 3125-40/30-30-30-30, 5' OCM,
ALL PRESSURES 0#
DST (3) 3133-50/30-30-30-30, 1778' GI,
310' GCO, 120' FROGGY MGCO, N/W,
SIP 782-657# FP 64-86# 118-164#
DST (4) 3331-38/30-30-30-30, 45' GO,
126' MO, 1819' VHOCM, N/W, SIP 118-
140# NO FFP, FSIP 559# (PLUGGED)
FP 118-140#, NO FFP
WICT - CO TD, TO 1750' OIL,
5 BOPH, N/W, T&R, POP