

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-22131-00-00
Spot: W2SENE Sec/Twnshp/Rge: 25-15S-14W
1980 feet from N Section Line, 1310 feet from E Section Line
Lease Name: BOOMHOWER A Well #: 5
County: RUSSELL Total Vertical Depth: 3378 feet

Operator License No.: 4419
Op Name: BEAR PETROLEUM, INC.
Address: PO BOX 438
HAYSVILLE, KS 67060

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	7	3374	1213	300 SX
SURF	10.75	901	0	475 SX

\$ 109.79

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/17/2006 9:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: BEAR PETROLEUM, INC. Phone: (620) 727-3410

Proposed Plugging Method: Ordered 400 sxs cement and 500# hulls.

Plugging Proposal Received By: BRUCE BASYE WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 05/17/2006 1:00 PM KCC Agent: ROGER MOSES

Actual Plugging Report:

Sanded 7" casing from 3378' to 3275' - followed with 7 sxs cement.
Cut 7" casing off at 1213' - pulled one joint and spotted 150 sxs cement with 250# hulls.
Pulled casing to 900' - spotted 50 sxs cement with 100# hulls.
Pulled casing to 260' - circulated with 125 sxs cement with 200# hulls.
Pulled remaining casing - cellar full of cement - plug complete.
Total of 332 sxs 60/40 pozmix - 10% gel - 500# hulls.

Perfs:

Top	Bot	Thru	Comments
3325	3326		

Remarks: QUALITY WELL SERVICE-WATER.

Plugged through: CSG

INVOICED
DATE 5-24-06
NO. 2006061696

District: 04

AD

Signed Roger Moses
(TECHNICIAN)

RECEIVED

MAY 24 2006

KCC WICHITA

Form CP-2/3


MAY 18 2006

PCT

SOLAR PETROLEUM, INC.
 999-18TH STREET, #1300 #5 "A" BOOMHOWER
 DENVER, CO 80202

25-15-14W
 1980'FNL&
 1310'FEL, NE/4

CONTR EMPHASIS OIL OPERATIONS CTY RUSSELL
 GEOL RICHARD G. SMITH FIELD TRAPP



ELV 1893 KB SPD 6/14/83 CARD ISSUED 9/8/83 IP P 2.28 BO &
1888 GL 111.72 BWPD
 API 15-167-22,131 ARB 3325-3326

LOG	Tops	Depth	Datum
*ANH		878 +	1015
*B ANH		915 +	978
1ST TARK SD		2470-	577
2ND TARK SD		2496-	603
TARK LM		2510-	617
ELM		2574-	681
HOW		2710-	817
TOP		2784-	891
HEEB		3011-	1118
TOR		3028-	1135
DOUG		3042-	1149
LANS		3076-	1183
BKC		3285-	1392
ARB		3322-	1429
RTD		3375-	1482
LTD		3378-	1485
* SAMPLE TOPS			

10 3/4 " 903/475SX, 7" 3374/300SX

DST (1) 3081-3109 (LKC B&C) / 15-60-60-120, REC 196' BBLS
 SW, SHOW OIL IN TOOL, SIP 624-604#, FP 29-49 / 79-128#,
 HP 1743-1733#, BHT 93'

DST (2) 3252-3272 (LKC K) / 15-60-60-120, REC 182' O & GCM,
 FREE OIL IN TOOL, SIP 751-801#, FP 29-29 / 49-49#, HP 1909-
 1870#, BHT 101'

MICT - CO. PF (ARB) 3325-26 W/4 SPF, AC 200G (15% HCL),
 LET SET OVERNIGHT, RE-AC 1000G (15% HCL), SWB DWN, SO,
 RE-AC 2500G (20% INS), SWB DWN, SO. POP. P 2.28 BO &
 111.72 BWPD, GTSTM, 7/26/83

COPYRIGHT 1983
 INDEPENDENT OIL & GAS SERVICE, INC.
 WICHITA, KANSAS