

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-22377-00-00
Spot: N2SWSWNE Sec/Twnshp/Rge: 33-15S-13W
3080 feet from S Section Line, 2316 feet from E Section Line
Lease Name: BERRY Well #: 1
County: RUSSELL Total Vertical Depth: 3349 feet

Operator License No.: 4419
Op Name: BEAR PETROLEUM, INC.
Address: PO BOX 438
HAYSVILLE, KS 67060

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3346	0	125 SX
SURF	8.625	450	0	250 SX

\$ 108.84

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/18/2006 1:00 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: JOE MAES Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: Ordered out 250 sxs 60/40 pozmix - 10% gel - 500# hulls.
Casing parted at 1000'.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 05/18/2006 4:00 PM KCC Agent: JAY PFEIFER

Actual Plugging Report:

Sanded off bottom to 3300' and topped with 5 sxs cement using a dump bailer.
Casing parted at 1000'.
Swaged onto 5 1/2" - mixed and pumped 100 sxs cement with 200# hulls.
Pulled up to 450' - spotted 40 sxs cement with 150# hulls.
Pulled up to 150' and circulated cement with 75 sxs.

Perfs:

Top	Bot	Thru	Comments
3346	3349		

Remarks: COPELAND ACID & CEMENTING.

Plugged through: CSG

INVOICED
DATE 5-24-06
2006061696

District: 04

HD.

Signed Jay Pfeifer (TECHNICIAN)

RECEIVED

MAY 24 2006

KCC WICHITA

Form CP-2/3

MAY 19 2006

PCT

replacement card

DERRICK-AMERICAN OIL, INC
WICHITA, KS 67202

33-15 -13W
110'N, C SW SW NE

#1 BERRY

site: 4-1/2 N & 5-1/2 W OF BEAVER, KS	city: RUSSELL	API 15-167-22377
contr: DUKE DRILLING CO.	field: TRAPP	
geol: ROBERT B. THOMPSON		
fr date 05/24/85	spd date 09/15/85	drig % comp 09/22/85
	card issued 06/13/85	last revised 01/27/88

ELV: NA SMP

tops.....depth/datum

ARB3346

RTD.....3349

IP status:

OIL WELL, ARB OH 3346-3349 ,

CSG: 8-5/8" 450, 5-1/2" 3346

NO CORES OR DSTS RPTD

MICT - CO, (ARB OH), SWB DWN, SO, POP, OIL WELL

(POTENTIAL NOT RPTD) - TIGHT HOLE - NO OTHER INFO

ON STATE RECORDS; NO OTHER INFO RELEASED BY

OPERATOR

INFO RELEASED: 1/27/88 - ADDED WELL INFO

NOTE: CORRECTION: 10/18/84 - ORIGINALLY FIRST

REPORTED AS C SW NE; 2/21/85 - ORIGINALLY FIRST

REPORTED AS FUTURE OIL & EXPLORATION, INC AS

OPERATOR, OPERATIONS TURNED OVER TO DERRICK-

AMERICAN AT CSG POINT

COPYRIGHT 1988
INDEPENDENT OIL & GAS SERVICE, INC.
WICHITA, KANSAS