

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-36348-00-00
Spot: SWSESW Sec/Twnshp/Rge: 9-11S-15W
330 feet from S Section Line, 1650 feet from W Section Line
Lease Name: JANTZEN Well #: 1
County: RUSSELL Total Vertical Depth: 3410 feet

Operator License No.: 5363
Op Name: BEREXCO, INC.
Address: PO BOX 20380
WICHITA, KS 67208

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	7	3401	0	300 SX CMT
SURF	10.75	1017	0	w/unknown sxs cmt

110.83

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/10/2006 1:00 PM
Plug Co. License No.: 99998 Plug Co. Name: COMPANY TOOLS
Proposal Rcvd. from: ROBERT GRANT Company: BEREXCO, INC. Phone: (785) 628-6101

Proposed
Plugging
Method:

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 05/10/2006 3:30 PM KCC Agent: CASE MORRIS

Actual Plugging Report:

Perforated at 250'.
Ran tubing to 2698'.
Pumped 160 sxs 60/40 pozmix - 10% gel cement with 600# hulls.
Pulled to 1350'.
Circulated with 160 sxs cement with 300# hulls.
POOH. Pumped 100 sxs cement down casing.
Max. P.S.I. 250#. S.I.P. 50#.
Bottom perforations were squeezed with cement prior to plugging operation.
Tagged cement at 2701'.
Well had other holes in casing at 1100'.

Perfs:

Top	Bot	Thru	Comments
3280	3286		
3262	3268		

INVOICED
DATE 5-24-06
2006061697

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

HD

Signed Case Morris
(TECHNICIAN)

RECEIVED
MAY 24 2006
KCC WICHITA

MAY 22 2006

PKT

INDEXED

BENNETT, LIGGETT, STEARNS #1

JANTZEN

33

9-11-15W
SW SE SW

Contr. STEARNS DRILLING COMPANY

RUSSELL

County

E 1935

Comm. 12-3-47

Comp. 4-2-48

IP 25 BOPD

Tops	Depth	Datum	Casing
ANH	1010	+925	20" 40
			15" 505 ACID 500
			13" 715
			10" 1017
			8" 2545
LANS	3065	-1130	7" 3401
ARB	3395	-1460	
T.D.	3410	-1475	

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS