

12-8 15-163-01819-00-00

To: 6 040994
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200, COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 1953
SW , SEC. 19, T. 8 S, R 17 W/E
990 feet from S section line
330 feet from W section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 3846

Lease Name Krug Well # 8
County Rooks 111.41
Well Total Depth 3428 feet
Conductor Pipe: Size feet

Operator: Tom Rush
Name & Address Box 322
Haysville, Ks. 67060

Abandoned Oil Well X Gas Well Input Well SWD Well D&A
Other well as hereinafter indicated
Casing: Size 8 5/8 feet 1319' w/600 sks

RECEIVED
STATE CORPORATION COMMISSION
JAN 18 1989
JAN 18 1989
CONSERVATION DIVISION
Wichita, Kansas

Plugging Contractor Allied Cementing License Number
Address Russell, Ks.

Company to plug at: Hour: Day: Month: Year: 19

Plugging proposal received from
(company name) (phone)

were: 5 1/2" casing set at 3409' w/150 sks. Top perf at 3129'. B.P. at 3370'.
Packer and tubing fish at 3267'. T.O.C. at 2762'. Ordered 275 sks 65/35 Poz 10% Gel 2% Lite w/1/4" F.C. plus 12 sks Hulls plus 50 sks common w/2% CC.

Plugging Proposal Received by Dennis L. Hamel
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part X None
Operations Completed: Hour: 5:00PM Day: 8 Month: 12 Year: 19

ACTUAL PLUGGING REPORT 5 1/2" casing ran tubing to 3100'. Pumped 50 sks common w/1 sk
Hulls, Disp w/gel. Pulled tubing to 2700'. Mixed and circulated gel to surface.

(40 sks gel w/6 sks Hulls). Pulled tubing to 1350'. Pumped 50 sks A.T.L. Cement w/1 sks Hulls. Pulled tubing to 700'. Pumped and circulated to surface w/125 sks A.T.L. Cement w/2 sks Hulls. Pulled tubing pumped add 25 sks A.T.L. Cement w/1 sk Hulls S.I. Psi 100#. 8 5/8" S.P. pumped 75 sks A.T.L. Cement w/2 sks Hulls S.I. psi 100#.

Remarks:
(If additional description is necessary, use BACK of this form.)

I (did / did not) observe this plugging.

INVOICED

DATE 1-20-89
INV. NO. 23717

Paul S.

Signed Dennis L. Hamel
(TECHNICIAN)
Dennis L. Hamel