

12-5 15-163-00287-00-00

To: 6 041103
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- NA
SW SW NW SEC. 19, T 8 S, R 17

2970 feet from S section line
2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5245

Lease Name Stamper Well # 1

Operator: Okmar Oil Co.

County Rooks 110.57

Name & Address

Box 723

Well Total Depth 3402 feet

Hays, Kansas 67601

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 148' w/75 sk

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor B. J. Titan License Number

Address Hays, Ks.

Company to plug at: Hour: 9:00 AM Day: 5 Month: Dec Year: 19 89

Plugging proposal received from George Jorgenson

(company name) Okmar Oil Co. (phone)

were: 5 1/2" casing set at 3397' w/200 sks cement. Perf at 3118 - 3318.

Sq at 823 - 864' w/773 sks cement. 4 1/2" liner from 1330' to surface.

5 1/2" casing collapsed at 2530'. Ordered 450 sks 65/35 poz 8% gel w/1/4" f.c. plus 5 sks hulls.

Plugging Proposal Received by Dennis L. Hamel (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 1:15PM Day: 5 Month: Dec Year: 19 89

ACTUAL PLUGGING REPORT Ran tubing to 2500': Spotted 150 sks 65/35 poz w/1/4" f.c. plus 100# hulls in cement: circ 1st 20 bbls. No circ next

18 bbls; Pulled tubing to 1200'. Pumped 225 sks 65/35 poz 8% gel w/1/4" f.c.

Cement circ pulled tubing filled casing w/cement. Hooked up to 8 5/8" s.p. Pumped

50 sks 65/35 poz 8% gel w/1/4" f.c. plus 100# hulls. Max 550# psi. S. DE 200#

Remarks: (If additional description is necessary, use BACK of this form.)

STATE CORPORATION COMMISSION
JAN 17 1990
JAN 17 1990

INVOICED (If additional description is necessary, use BACK of this form.)

CONSERVATION DIVISION
Wichita, Kansas

DATE JAN 24 1990

Signed Dennis L. Hamel (TECHNICIAN)

INV. NO. 27138

FEB 09 1990