

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-20970-00-01
Spot: NENWNESE Sec/Twnshp/Rge: 30-11S-19W
2540 feet from S Section Line, 900 feet from E Section Line
Lease Name: ZERFAS Well #: 2
County: ELLIS Total Vertical Depth: 3781 feet

Operator License No.: 30606
Op Name: MURFIN DRILLING CO., INC.
Address: 250 N. WATER, STE 300
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	1432	0	400 SX CMT

\$ 122.88

Well Type: SWD UIC Docket No: D15528.0 Date/Time to Plug: 05/19/2006 9:00 AM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: MIKE STANTON Company: MURFIN DRILLING CO., INC. Phone: (785) 483-9633

Proposed Plugging Method: Ordered 125 sxs 60/40 pozmix - 10% gel - 500# hulls.
Perfs at 1090' - 1150'.

Plugging Proposal Received By: HERB DEINES WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 05/19/2006 11:30 AM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Allied pumped 100 sxs 60/40 pozmix - 10% gel with 500# hulls.
Max. P.S.I. 1000#. S.I.P. 500#.

Perfs:

Top	Bot	Thru	Comments
1090	1150		

Remarks: KELLER - WATER.

Plugged through: CSG

INVOICED

5-24-06
2006061703

District: 04

Signed

Richard Williams

(TECHNICIAN)

RECEIVED

MAY 24 2006

KCC WICHITA

Form CP-2/3

MAY 19 2006

PKT

MURFIN DRILLING CO. #2 ZERFAS "TWIN" 30-11-19W
 617 UNION CENTER, WICHITA, KS. APP NW NE SE
 CONTR. CO. TOOLS CTY. ELLIS

GEOL. _____ FIELD ZERFAS
 E 2126 KB c/w/17/74 CARD ISSUED 8/1/74 IP D&A/ARB
 7/28/74

+	+	+
+	+	+
+	+	+

API 15-051-20,970

SMP	TOPS	DEPTH	DATUM
ANH		1472	+ 654
B ANH		1515	+ 611
TOP		3112	- 986
HEEB		3332	-1206
TOR		3351	-1225
LKC		3373	-1247
BKC		3593	-1467
MARM		3625	-1499
ARB		3681	-1555
ID		3781	-1655

8-5/8" 171/150sx
 NO LOG
 DST (1) 3132-3146/30-30, REC 65' WM,
 BHP 1009-0#, FP 47-48#
 DST (2) 3362-3415/30-30-30-30, REC 390'
 WOSM, BHP 1067-997#, FP 106-165#
 DST (3) 3415-3435/30-30-30-30, REC 60'
 OWM, 770' MW, BHP 1136-1125#, FP
 248-379#
 DST (4) 3436-3445/30-30-30-30, REC
 625' G, 295' CO, BHP 1113-1078#, FP
 33-82#
 DST (5) 3449-3470/30-30-30-30, REC
 1300' SW, BHP 1113-974#, FP 402-
 578#
 DST (6) 3488-3552/30-30-30-30, REC 185'
 SOCM, 280' O SP MW, BHP 1171-1125#

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS