

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-109-20765-00-00
Spot: NWNENE Sec/Twnshp/Rge: 6-11S-33W
330 feet from N Section Line, 1050 feet from E Section Line
Lease Name: DUMLER AD Well #: 1
County: LOGAN Total Vertical Depth: 4760 feet

Operator License No.: 3988
Op Name: SLAWSON EXPLORATION COMPANY,
Address: 204 N ROBINSON, STE 2300
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	309		

154.70

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 05/21/2006 12:00 PM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: GREH UNRUH Company: MURFIN DRILLING CO., INC. Phone: (316) 267-3241

Proposed Plugging Method: Ordered 200 sxs 60/40 pozmix - 6% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: CASE MORRIS WitnessType: NONE
Date/Time Plugging Completed: 05/21/2006 3:30 PM KCC Agent: CASE MORRIS

Actual Plugging Report:

No Arbuckle cut.
1st. Plug at 2680' w/25 sxs.
2nd. Plug at 1750' w/100 sxs.
3rd. Plug at 360' w/40 sxs.
4th. Plug at 40' w/10 sxs.
Rathole with 15 sxs.
Mousehole with 10 sxs.

Perfs:

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

INVOICED
DATE 5-24-06
INV. NO. 2006061707

District: 04

HO

Signed Case Morris
(TECHNICIAN)

RECEIVED
MAY 24 2006
KCC WICHITA

MAY 22 2006

PCT