

15-163-01333-00-00

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission  
Conservation Division  
211 North Broadway  
Wichita, Kansas

FILE NO. 122-58

LOCATION SE NW SE

SEC. 33 TWP. 8 RGE. 16 W

Dry Hole \_\_\_\_\_ Abandoned Oil Well <sup>X</sup> \_\_\_\_\_ Abandoned Gas Well \_\_\_\_\_

I have this date completed supervision of plugging of:

Well No. C-1 Lease Adams

Operator Cities Service Oil Address Box 556 Russell, Kans

Field \_\_\_\_\_ County Rooks

Total Depth 3295 Feet.

Plugging Contractor Jack Shull

Plugging Contractor's License No. 8

Address \_\_\_\_\_

(Describe briefly the manner in which the well was plugged)

8 5/8" at 220' circulated with cement - 4 1/2" at 3295' with 12s

sax cement behind - cement to 3278' perforated at 3260' & 3165'

filled with cement to 3038'.

Pulled 350' 4 1/2" - filled with mud to 220', set rock and 15 sax

cement - mud to 35', set rock and 10 sax cement to bottom cellar.

District Conservation Agent

Date 6-21-55

**PLUGGING**  
FILE SEC 33 T 8 R 16 W  
BOOK PAGE 122 LINE 38

STATE OF KANSAS  
JUN 23 1955  
CONSERVATION DIVISION  
Wichita, Kansas  
6/29/55