

15-163-01340-00-00

DISTRICT CONSERVATION AGENT'S REPORT

*R*

TO:

State Corporation Commission  
Conservation Division  
800 Bitting Building  
Wichita, Kansas

FILE NO. \_\_\_\_\_

LOCATION CS $\frac{1}{2}$  SE SE

SEC. 34 TWP. 8 RGE. 16 *w*

Dry Hole \_\_\_\_\_ Abandoned Oil Well X Abandoned Gas Well \_\_\_\_\_

I have today completed supervision of plugging of:

Well No. 1 Lease Doane

Operator Max Cohen Address 203 *B...* *Clay*  
Wichita, Kans

Field \_\_\_\_\_ County Rooks

Total Depth 3140 Feet.

(Describe briefly the manner in which the well was plugged)

5  $\frac{1}{2}$ " at 3140'. Perforations at 3094'.

Filled with sand to 3090', set 4 sax cement with dump bailer.

pulled 2100'  $5\frac{1}{2}$ ", pumped hole full mud and pumped 20 sax cement in

hole at 200' *thru casing*, filled with mud to 20', set rock bridge and 10 sax

cement to bottom cellar.

\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

PLUGGING  
FILE SEC 34 T 8 R 16  
BOOK PAGE 140 LINE 6

*[Signature]*  
District Conservation Agent

Date 10-20-51

*10/27/51*

*F*