

15-163-00309-00-01

Form CP-3
Rev. 6-26-62KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, KansasRECEIVED
STATE CORPORATION COMMISSION

3/15/63 MAR 15 1963

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Mutual Oil Co

Complete Address: Box 502 Salina, Kansas

Lease Name Diehl Well No. 1

Location NE NE SW Sec. 34 Twp. 8 Rge. (E) (W) 17

County Rooks Total Depth 3466

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: reopened hole

Plugging Contractor: Barnes & Sons & Globe Cementing Co

Address: Russell, Kansas License No. 9

Operation Completed: Hour 3PM Day 9 Month 3 Year 63

The Above well was plugged as follows:

8 5/8" 164' circulated with cement - 4 1/2" 3466' with 200 sax cement .
 Perf ? - set plug at 3150', sand to 3100', set 3 sax cement with dump
 bailer.

Pulled 2800' 4 1/2" to 550', circulated hole with heavy mud through 4 1/2"
 (31 sax Gel), displaced 20 sax cement through 4 1/2" at 550', heavy mud to
 165', displaced 20 sax cement through 4 1/2" at 165', heavy mud to 35',
 cement 35' to bottom cellar.

Mudding and cementing by Globe Cementing Co.

I hereby certify that the above well was plugged as herein stated.

DATE 3/15/63
 INV. NO. 6922-W

Signed: Edson P. [Signature]
 Well Plugging Supervisor