

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

MAR 10 1978
3-10-78

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 - 163 - 20,777-00-00 (of this well)

Operator's Full Name Dreiling Oil, Inc.

Complete Address R. R. #1, Victoria, Kansas

Lease Name Schindler Well No. 1

Location SE NE NE Sec. 27 Twp. 8 Rge. (E) (W) 17

County Rooks Total Depth 3490'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Co. Tools.

Address License No.

Operation Completed: Hour 8:30 A Day 9 Month 3 Year 1978

The above well was plugged as follows:

RTD 3490' 8 5/8 csg set 166' cwc 125 sk. Plg. Mat. 50-50 poz 2% total gel.

Gunned pits, circulated heavy mud, set 70 sk cmt plug at 550' thru drill pipe.

Heavy mud to 160' set 20 sk cmt plug thru drill pipe. Heavy mud to 40' set solid

bridge & 10 sk cmt plug to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: L. S. Massey
Well Plugging Supervisor

DATE 3-10-78

INV. NO. 6906-W