

15-163-20815-00-00

f

KANSAS

Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
245 North Water  
Wichita, KS 67202

API Number 15 - 163 - 20,815

STATE RECEIVED  
STATE CORPORATION COMMISSION

JUN 27 1978  
CONSERVATION DIVISION  
Wichita, Kansas  
6-27-78

Operator's Full Name Thomas E. Black d/b/a Black Petroleum Co.

Complete Address 545 O. W. Garvey Bldg., Wichita, Kansas

Lease Name Bemis "A" Well No. 1

Location C W/2 W/2 SE/4 Sec. 27 Twp. 8 Rge. (E) (W) 17

County Rooks Total Depth 3480'

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A XX

Other well as hereafter indicated       

Plugging Contractor Shields Drlg.

Address        Russell, Kansas License No.       

Operation Completed: Hour 3:45 P Day 25 Month 6 Year 1978

The above well was plugged as follows:

RTD 3480' 8 5/8 csg. set 250' cwc 160 sk. Plg. Mat. 50-50 poz 6% total gel.

Gunned pits, circulated heavy mud, set 70 sk cmt plug at 550' thru drill pipe.

Heavy mud to 240' set 20 sk cmt plug thru drill pipe. Heavy mud to 40' set solid

bridge & 10 sk cmt plug to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]  
Well Plugging Supervisor

DATE 6-28-78

INV. NO. 7586.42