

DISTRICT CONSERVATION AGENT'S REPORT

BR

TO:

15-163-00676-00-00

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 45-20
LOCATION SW SW NW
SEC. 20 TWP. 8 RGE. 17

Dry Hole x Abandoned Oil Well _____ Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 1 Lease Stamper

Operator United Drg Co Address Russell, Kans

Field _____ County Rooks

Total Depth 3383 Feet.

Plugging Contractor Jayhawk Pipe Pulling & Halliburton Co

Plugging Contractor's License No. 19

Address _____

(Describe briefly the manner in which the well was plugged)

8 5/8" at 164' circulated with cement - 5 1/2" at 3327'
with 100 sax cement behind.

Filled with sand to 3315', set 4 sax cement with dump bailer,
pulled 2500' 5 1/2", pumped hole full commercial mud (25 sax).

Pumped cementing plug to 160', followed by 50 sax cement.
Cement 160' to 0'.

Mudding and cementing by Halliburton Cementing Co.

PLUGGING
FILE SEC 20 TWP 8 RGE 17
BOOK PAGE 45 LINE 20

RECEIVED
STATE CORPORATION COMMISSION
John L. Perry
District Conservation Agent
JUL 13 1954
Date 7-10-54
CONSERVATION DIVISION
Wichita, Kansas

7-13-54