

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

15-163-20401-00-00

RECEIVED
STATE CORPORATION COMMISSION
JAN 10 1972
CONSERVATION DIVISION
Wichita, Kansas

1-10-72

Operator's Full Name Gemini Corporation

Complete Address Box 818 McCook, Nebraska

Lease Name Reeder Well No. 1

Location C NW NE NW Sec. 20 Twp. 8 Rge. (E) (W) 17

County Rooks Total Depth 3364'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Shields Drilling

Address Russell, Kansas License No.

Operation Completed: Hour 10:15 P Day 5 Month 1 Year 1972

The above well was plugged as follows:

RTD 3364' 8 5/8 csg set at 257' cwc Cmt. Mat. 50-50 poz cmt W/4% added gel.

Gunned pits, circulated heavy mud, set cementing plug at 660' and displaced 70 sk

cmt thru drill pipe. Heavy mud to 240' set cementing plug and displaced 20 sk cmt

thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to

base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Reed Massey
Well Plugging Supervisor

DATE 1-13-72

INV. NO. 4978-W