

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

15-163-20887-00-00

API Number 15 -163 -20,887 (of this well)

Operator's Full Name Ruggels Chesney Oil Co.

Complete Address Box 254, Natoma, Ks.

Lease Name Larsen "A" Well No. 1

Location NE NE SE Sec. 22 Twp. 8 Rge. (E) (W) 17

County Rooks Total Depth 3150'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Lawbanco Drlg. Co.

Address Hill City, Ks. License No.

Operation Completed: Hour 3:30 P Day 31 Month XX 1 Year 1979

The above well was plugged as follows:

RTD 3150' 8 5/8 csg set 208' cwc. Plg. Mat. 50-50 poz 6% total gel.

Gunned pits, circulated heavy mud, set 70 sk cmt plug at 650' thru drill pipe.

Heavy mud to 200' set 20 sk cmt plug thru drill pipe. Heavy mud to 40' set solid

bridge & 10 sk cmt plug to base of cellar.

RECEIVED
STATE CORPORATION COMMISSION

FEB - 2 1979

CONSERVATION DIVISION
Wichita, Kansas

2-2-79

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 2-2-79

INV. NO. 9059-W

Signed: Leo Massey
Well Plugging Supervisor