

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market - Room 2078
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

RECEIVED

API NUMBER 15-189-20078-0000

LEASE NAME PETTIJOHN

WELL NUMBER 2-10

1400' FNL Ft. from S Section Line

1400' FWL Ft. from E Section Line

SEC. 10 TWP. 31S RGE. 39W (E) or (W)

COUNTY STEVENS

Date Well Completed 12/29/69

Plugging Commenced 5/22/06

Plugging Completed 5/22/06

LEASE OPERATOR PIONEER NATURAL RESOURCES USA, INC.

ADDRESS 5205 N. O'CONNOR BLVD., ROOM 1325 - IRVING, TX 75039

PHONE # 072) 444-9001 OPERATORS LICENSE NO. 4824

Character of Well GAS

(Oil, Gas, O&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 04/21/06 (date)

by DAVID WILLIAMS (KCC District Agent's Name)

is ACO-1 filed? YES If not, is well log attached? _____

Producing Formation CHASE Depth to Top 3189' Bottom 2917' T.D. 2925'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| Formation | Content | From | To | Size | Put in | Pulled out |
|-----------|---------|-------|-------|--------|--------|------------|
| CHASE | GAS | 2736' | 2897' | 8 5/8" | 608' | 0' |
| | | | | 5 1/2" | 2924' | 959' |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from ___ feet to ___ feet each set

4/27/06-Set CIBP @2675' KB, spot 20' cmt. Revise PBTD @2655'. 5/22/06 J Holland, KCC witness-RIH & cut 5 1/2" csg @ 959'. NU cmtr & load hole w/40 bbl mud & 30 sx cmt 950'-850' & 20 bbl mud. Pmp 50 sx cmt plug frm 630'-480'. Displ w/12 bbl mud, fill csg w/mud to 40'. Pmp 10 sx cmt 40'-0'. Cut 8 1/2" csg 3' bgl, weld on trash cover - ID plate.

Name of Plugging Contractor SARGENT AND HORTON PLUGGING INC. License No. 31151

Address RT. 1, BOX 49BA TYRONE OK 73951-9731


NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: PIONEER NATURAL RESOURCES USA, INC.

STATE OF TEXAS COUNTY OF DALLAS, ss.

LINDA KELLY (Employee of Operator) or (Operator) of above-described well, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Linda Kelly

(Address) 5205 N. O'CONNOR BLVD. RM 1325 IRVING TX 75039



ANGIE G. HERNANDEZ
Notary Public, STATE OF TEXAS
My Commission Expires
JULY 14, 2009

AND SWORN TO before me this 25 day of May, 20 06

My Commission Expires: 7-14-2009 Angie G. Hernandez Notary Public

USE ONLY ONE SIDE OF EACH FORM

RECEIVED

MAY 30 2006

KCC WICHITA

Form CP-4
Revised 05-88

AKT