

STATE OF KANSAS  
STATE CORPORATION COMMISSION


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas

WELL PLUGGING RECORD

Rooks

County. Sec. 19 Twp. 8 Rge. 17 (E)W (W)

NORTH



Locate well correctly on above  
Section Flat

Location as "NE/CNW%SW%" or footage from lines SW $\frac{1}{4}$  SW $\frac{1}{4}$  NW $\frac{1}{4}$

Lease Owner V.D. Sidey Oil Company

Lease Name V.D. Sidey Oil Co-Schindler Well No. 2

Office Address Russell, Kansas.

Character of Well (completed as Oil, Gas or Dry Hole) Oil well

Date well completed \_\_\_\_\_ 19\_\_\_\_

Application for plugging filed \_\_\_\_\_ 19\_\_\_\_

Application for plugging approved \_\_\_\_\_ 19\_\_\_\_

Plugging commenced Oct. 11 19 54

Plugging completed Oct. 17 19 54

Reason for abandonment of well or producing formation Exhaustation of

oil

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes.

Name of Conservation Agent who supervised plugging of this well Eldon Petty

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3432 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from 3432 feet to surface feet for each plug set.

Wooden plug set at 3120 ft; hole filled with sand from 3120 to 3100; four sacks of cement placed in hole with dump bailer to form cement plug from 3100 to 3068; hole filled with mud from 3068 to 150 feet; ten foot rock bridge installed; fifteen sacks of cement poured in hole, and hole mudded to 30 ft; five foot rock bridge installed between 30 and 25 feet; hole filled to top of 8 5/8 inch pipe and capped with ten sacks of cement.

OCT 27, 1954

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Barnes and Sons Pipe Pulling Co

Address Russell, Kansas.

STATE OF KANSAS, COUNTY OF RUSSELL, ss.  
V. D. Sidey (~~Employee of~~ owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.


(Signature) V. D. Sidey

(Address)

SUBSCRIBED AND SWORN to before me this 26th day of October, 19 54

My commission expires September 17, 1956

Marquitta Byrne  
Notary Public.



# SIDEY DRILLING COMPANY

BUILDING & LOAN BLDG. P. O. BOX 387

RUSSELL, KANSAS

COMPANY V. D. Sidey Oil Company

SEC. 19 T. 8 R. 17W  
LOC. SW SW NW

FARM Schindler NO. 2

TOTAL DEPTH 3425  
COMM. 4-25-52 COMP. 5-7-52  
SHOT OR TREATED  
CONTRACTOR Sidey Drilling Company  
ISSUED

COUNTY Rooks

CASING	
20	10
15 1/2	8 1/4 131'
12 1/2	6 5/8
13 3/8	5 5/16 3423'

ELEVATION 1991 DF  
1998 Gr

PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS

45	Sand & shale
50	sand
131	shale
215	black shale
300	shale
310	shale and shells
340	shale
460	shale & shells
490	sand
515	shale
660	sand
750	shale
765	sand
845	shale
970	sand
1040	red bed
1090	red shale
1160	shale and shells
1200	sand and shale
1318	shale and shells
1345	Anhydrite
1575	shale and shells
1900	shale and lime
1995	lime
2000	shale
2055	lime
2100	lime and shale
2190	broken lime
2285	lime
2365	lime and shale
3170	lime
3300	lime and shale
3425	lime TD

STATE OF KANSAS )  
COUNTY OF RUSSELL) ss.

I, V. D. Sidey, of the Sidey Drilling Company, upon oath state that the above and foregoing is a true and correct copy of the log of the Schindler # 2 well.

*Received Oct 27, 1954*

**PLUGGING**  
 FILE SEC. 19 T. 8 R. 17W  
 BOOK PAGE 68 LINE 31

*V. D. Sidey*  
V. D. Sidey

Subscribed and sworn to before me this 5<sup>th</sup> day of October, 1954.

*Marguerite Byrnes*  
Notary Public

My Commission Expires: *Sept. 17, 1956*