

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Bldg.  
Wichita, Kansas 67202

COPY

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit

COUNTY Rooks SEC. 19 TWP. 8 RGE. 7 N/W  
Location as in quarters or footage from lines:  
NE/4 NE/4 NE/4


Locate Well  
correctly on above  
Section Platt.

Lease Owner Thomas E. Brown d/b/a The Gene Brown Company  
Lease Name Stamper Well No. 1  
Office Address 407 S. Main, Plainville, Kansas 67663  
Character of Well (Completed as Oil, Gas or Dry Hole): Oil  
Date Well Completed Sept. 4 1980  
Application for plugging filed Verbal  
Plugging commenced May 30, 1985  
Plugging completed May 30, 1985  
Reason for abandonment of well or producing formation  
Lost tubing in hole due to sand  
Was permission obtained from the Conservation Division or it's  
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Dennis Hamel  
Producing formation Arbuckle Depth to top 3329 bottom 3380 T.D. 3380  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
Surface				8 5/8"	156	none
Production				4 1/2"	3379	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set. Foreign water broke through casing at 900' and 1159' from surface. Could not recover 300' of tubing.  
Pumped 50 sacks cement then 200 sacks cement with hulls down 4 1/2 casing, then pumped 100 sacks cement with hulls down 8 5/8" surface pipe. Cement stayed within 5' of surface.


Cement order on location 350 sacks 60/40 pos-10% gel 3% c.c. and 6 sacks hulls

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Halliburton Services

STATE OF Kansas COUNTY OF Rooks, ss.  
Thomas M. Brown (employee of owner) ~~owner~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Thomas E. Brown  
407 S. Main, Plainville, Kansas  
(Address) 67663

SUBSCRIBED AND SWORN TO before me this 2 day of July, 1985



My Commission expires

Kathy A. Wise  
Notary Public

RECEIVED  
STATE CORPORATION COMMISSION

AUG 20 1985  
AUG 20, 1985