

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, KS 67202

WELL PLUGGING RECORD

K.A.R.-82-3-117

15-163-19127-00-01

NUMBER 15 N/A

LEASE NAME Reeder

TYPE OR PRINT

WELL NUMBER 2

NOTICE: Fill out completely and return to Cons. Div. Office within 30 days.
1320 Ft. from S Section Line
2310 Ft. from E Section Line

LEASE OPERATOR OXY USA Inc.

SEC. 19 TWP. 8S RGE. 17 (X) or (W)

ADDRESS P. O. Box 26100

COUNTY Rooks

PHONE# (405) 749-2309 Operators License #5447

Date Well Completed 12/28/53

Character of Well Oil

Plugging Commenced 4/18/94

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 4/25/94

The plugging proposal was approved on 3/14/94 (date)

by Marion Schmidt (KCC District Agent's name)

Is ACO-1 filed? No If not, is well log attached? No

Producing Formation Arbuckle Depth to Top 3085 Bottom 3290 T.D. 3393

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled Out
Arbuckle	Oil	3085	3393	8 5/8	240	
				5 1/2	3372	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from ___ feet to ___ feet each set.

Setup to perf 5 1/2 csg. Hit tight spot @853. Could not get below 853'. Ran 2 1/2 tbg. w/3 7/8 bit to 853 tag tight spot. Drilled to 855 & fell thru. Ran tbg. to 1220 hit tight spot. Drilled to 1250. Drilled from 1250 to 1270 bit locked up tried to pull tbg. Tbg. stuck. Cement state plugger. Perf w/2 spt @ 1228, 1226. Acidized perf w/28% HCL. (See Back of form)
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Express Well Service License No. 6426

Address P. O. Box 426, Victoria, Ks 67671

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: OXY USA Inc.

STATE OF OKLAHOMA COUNTY OF OKLAHOMA, ss.

Jerry Ledlow (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature)

(Address) P. O. Box 26100, OKC, OK 73126-0100

SUBSCRIBED AND SWORN TO before me this 2nd day of May 19 94

Notary Public

My Commission Expires 8-21-96

JUL 12 1994 Form GP-4
JUL 12 1994 Revised 05-88
CONSERVATION DIVISION
Wichita