


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Rooks County. Sec. 19 Twp. 8 Rge. 17 (E) W (W)
Location as "NE/CNW/SW" or footage from lines NE/4 SW/4 NW/4
Lease Owner V.D. Sidey Oil Co., Russell, Kansas.
Lease Name V.D. Sidey Oil Co-Schindler Well No. 3.
Office Address Russell, Kansas.
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced Jan 10, 1956 19____
Plugging completed Feb. 12, 1956 19____
Reason for abandonment of well or producing formation _____



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3414 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from 3414 feet to Surface, feet for each plug set.

Hole filled with sand from 3414 to 3400; Four sacks of cement dumped with dump hauler to form cement plug from 3400 to 3368; Pumped thirty sacks of mud and fifty sacks of cement with Hailiburton pump trucks into hole, with plug pumped down between mud and cement; plugging complete.

(If additional description is necessary, use BACK of this sheet)


Name of Plugging Contractor Barnes and Sons Pipe Pulling Co
Address Russell, Kansas.

STATE OF KANSAS, COUNTY OF RUSSELL, ss.
V. D. Sidey (~~employee of~~ owner) (~~operator~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) V. D. Sidey
Box 387 Russell, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 8th day of March, 1956

My commission expires September 17, 1956 Margaret Barnes Notary Public.



CONSERVATION DIVISION
MAR 9 - 1956
Wichita

15-163-02990-00-00

SIDEY DRILLING COMPANY

BUILDING & LOAN BLDG. P. O. BOX 387

RUSSELL, KANSAS

COMPANY V. D. Sidey Oil Company

SEC. 19 T. 8S R. 17W
LOC. SE SW NW

FARM Schindler NO. 3

TOTAL DEPTH 3410'
COMM. 5-17-53 COMP. 5-29-53
SHOT OR TREATED
CONTRACTOR Sidey Drilling Company
ISSUED

COUNTY ROOKS

CASING
20 10
15 1/2 8 1/4 106'
12 1/2 6%
18% 5 5/16 3410'

ELEVATION 1978 DT
1976 Gr

PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS

0-45	Shale & Chalk Rock	2900-2955	Lime
45-50	Sand	2955-3130	Lime & Shale
50-106	Shale & Shells	3130-3410	Lime T. D.
106-210	Shale		
210-450	Shale & Shells		
450-459	Sand		
459-535	Shale & Shells		
535-573	Sand		
573-800	Shale & Shells		
800-810	Iron & Hard Sand		
810-830	Shale & Shells		
830-850	Sand & Shale		
850-950	Sand		
950-1020	Sand & Shale		
1020-1215	Shale & Red Bed		
1215-1310	Shale & Red Rock		
1310-1348	Anhydrite		
1348-1410	Shells		
1410-1655	Shale & Shells		
1655-1715	Salt		
1715-1820	Shale & Shells		
1820-1845	Lime		
1845-1925	Shale & Lime		
1925-2220	Lime		
2220-2900	Lime & Shale		

STATE OF KANSAS)
COUNTY OF RUSSELL) ss.

I, V. D. Sidey, of the Sidey Drilling Company, upon oath state that the above and foregoing is a true and correct copy of the log of the Schindler #3 well.

V. D. Sidey
V. D. Sidey

Subscribed and sworn to before me this 19th day of June, 1953.

Margaret Bryan
Notary Public

My Commission Expires: Sept. 17, 1956

MAR 9 - 1956

PLUGGING
WELL SEC. 19 T. 8S R. 17W
ROCK FAC. 43 LINE 8

CONSERVATION DIVISION
Wichita, Kansas