

STATE OF KANSAS
ATE CORPORATION COMMISSION
J S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-163-22, 186-00-00

LEASE NAME Schindler B

WELL NUMBER 4

4950 Ft. from S Section Line

3630 Ft. from E Section Line

SEC. 19 TWP. 8 RGE. 17 or (W)

COUNTY Rooks

Date Well Completed 10-31-83

Plugging Commenced 08-06-02

Plugging Completed 08-06-02

EASE OPERATOR The Don Brown Company

ADDRESS PO Box 24 Plainville, Ks 67663

PHONE# (785) 434-4944 OPERATORS LICENSE NO. 31013

Character of Well oil

(Oil, Gas, D&A, SMD, Input, Water Supply Well)

The plugging proposal was approved on 08-06-02 (date)

by Dennis Hamel (KCC District Agent's Name).

Is ACO-1 filed? yes If not, is well log attached? _____

Producing Formation Toronto L/KC Depth to Top 3115 Bottom 3338 T.D. 3399

How depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| Formation | Content | From | To | Size | Put In | Pulled out |
|-----------|-----------|------|------|-------|--------|------------|
| Toronto | Oil/water | 0 | 175 | 8 5/8 | 175 | |
| KC | Oil/water | 0 | 3409 | 5 1/2 | 3409 | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from ___ feet to ___ feet each set

Ran tubing to 1200' pump 250 sks w/400# hulls Circ cmt pull tubing pump down 5 1/2 w/35 sks cmt press to 400# shut in pump down annulus w/25 sks cmt w/100# hulls press to 200# shut in

Name of Plugging Contractor Allied Cementing Co License No. _____

Address PO Box 31 Russell Kansas 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Don Brown

STATE OF Kansas COUNTY OF Rooks, ss.

Don Brown (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.

(Signature) Don Brown

(Address) PO Box 24 Plainville Ks 67663

KCC


SUBSCRIBED AND SWORN TO before me this 16th day of August, 2002

AUG 21 2002

Bonita K. Shubert
Notary Public

My Commission Expires: 8-21-2005

HAYS, KS



Form CP-4
Revised 05-88

OR