

STATE OF KANSAS  
 STATE CORPORATION COMMISSION  
 200 Colorado Derby Building  
 Wichita, Kansas 67202

WELL PLUGGING RECORD  
 K.A.R.-82-3-117

LEASE NAME \_\_\_\_\_  
 API NUMBER 15-163-21,290-00-00  
 LEASE NAME Schindler  
 WELL NUMBER B-1

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

330' 660' HBE 8 1/2" x 100'S  
330' 2970' Ft. from S Section Line  
2970' Ft. from E Section Line  
 SEC. 19 TWP. 8 RGE. 17 (E) or (W)  
 COUNTY Rooks  
 Date Well Completed 4-22-81  
 Plugging Commenced 8-15-96  
 Plugging Completed 8-15-96

LEASE OPERATOR The Don Brown Company

ADDRESS PO Box 24 Plainville, Ks 67663

PHONE# (913) 424-2796 OPERATORS LICENSE NO. 31013

Character of Well oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 8-15-96 (date)

by Verbal approval by Herb Deines Emergency plugging (KCC District Agent's Name).

Is ACO-1 filed? \_\_\_\_\_ If not, is well log attached? Yes

Producing Formation KC - ARB Depth to Top 3141 Bottom 3440 T.D. 3452

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Received:  
 1996 Aug 21

Formation	Content	From	To	Size	Put in	Pulled out
LKC	Oil & Water	0	160	8 5/8	160'	0
ARB	Oil & Water	0	3470	4 1/2	3469'	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.  
Ran in 2 3/8" tbg to 2034' mix 100 sks 60/40 poz 10% jel 1/4# flocliel w/300# hulls pump down blow on backside, pull tbg to 1086' mix 50 sks cmt w/100# hulls cmt trying to circ pull pull tbg to 500' mix 50 sks cmt w/100# hulls cmt circ to surface pulled tubing out of hole pumped 10 sks down 4 1/2" 40 sks in 8 5/8" both had 300# close-in pressure  
 (If additional description is necessary, use BACK of this form.)


Name of Plugging Contractor Halliburton Services License No. \_\_\_\_\_

Address Hays Ks 67601

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: The Don Brown Company

STATE OF Kansas COUNTY OF Rooks, ss.

Don Brown (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.



(Signature) Don M. Brown  
 (Address) P.O. Box 24 Plainville, Ks 67663

SUBSCRIBED AND SWORN TO before me this 19<sup>th</sup> day of August, 19 96

Bonita K. Schubert  
 Notary Public

My Commission Expires: July 2, 1997