

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION OIL & GAS CONSERVATION DIVISION WELL PLUGGING RECORD K.A.R. 82-3-117

Form CP-4 December 2003 Type or Print on this Form Form must be Signed All blanks must be Filled

Lease Operator: Abercrombie Energy, LLC
Address: 150 N. Main, Suite 801, Wichita KS, 67202
Phone: (316) 262-1841 Operator License #: 32457
Type of Well: D&A Docket #:
The plugging proposal was approved on: 5/15/06
by: Eric MacLaren
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)

API Number: 15-101-21923-0000
Lease Name: Baier
Well Number: 1-6
Spot Location (QQQQ): approx. SE SE NW
2090 Feet from North / South Section Line
3075 Feet from East / West Section Line
Sec. 6 Twp. 18 S. R. 30 East West
County: Lane
Date Well Completed: 5/17/06
Plugging Commenced: 5/16/06
Plugging Completed: 5/17/06

Show depth and thickness of all water, oil and gas formations.

Table with 7 columns: Oil, Gas or Water Records (Formation, Content) and Casing Record (Surface Conductor & Production) (From, To, Size, Put In, Pulled Out). Row 1: surface, 266', 8 5/8", 253', 0.0

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

1st plug @ 2280' w/50 sx, 2nd plug @ 1530' w/50 sx, 3rd plug @ 750' w/50 sx, 4th plug @ 300' w/ 50 sx, 5th plug @ 60' w/ 20 sx, 15 sx in rathole, 10 sx in mousehole. Total of 245 sx of 60/40 Poz, 6% gel & 1/4# flocele. Final plug down at 7:15 am on 5/17/06. Job by Jet Star.

Name of Plugging Contractor: Val Energy, Inc. License #: 5822

Address: 215 N. Water, Ste 15, Wichita, KS., 67202

Name of Party Responsible for Plugging Fees: Abercrombie Energy, LLC.

State of Kansas County, Sedgwick, ss.

Don Beauchamp (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) [Handwritten Signature]
(Address) 150 N. Main, Wichita, KS 67202

SUBSCRIBED and SWORN TO before me this 19th day of May, 2006

[Handwritten Signature] My Commission Expires: 4-15-2010
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

DEBORAH A. MARTIN
Notary Public - State of Kansas
My Appt. Expires 4-15-2010

RECEIVED
JUN 01 2006
KCC WICHITA

PKT