

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-111-19007-00-00
Spot: SESENE Sec/Twnshp/Rge: 31-21S-12E
3174 feet from S Section Line, 296 feet from E Section Line
Lease Name: NUESSEN Well #: B 3
County: LYON Total Vertical Depth: 1908 feet

Operator License No.: 6470
Op Name: SCHANKIE WELL SERVICE, INC.
Address: 1006 SW BLVD.
MADISON, KS 66860

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	1903		
SURF	8.625	106		

\$ 62.01

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/16/2006 8:00 AM
Plug Co. License No.: 6470 Plug Co. Name: SCHANKIE WELL SERVICE, INC.
Proposal Rcvd. from: CLIFFORD SCHANKIE Company: SCHANKIE WELL SERVICE, INC. Phone: (620) 437-2595

Proposed Plugging Method: 50' CEMENT PLUG AT 1850', 50' CEMENT PLUG AT 900', 150' CEMENT PLUG TO SURFACE.

Plugging Proposal Received By: MICHAEL HEFFERN Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 03/17/2006 5:00 PM KCC Agent: MICHAEL HEFFERN

Actual Plugging Report:

HIT BRIDGE IN CASING AT 570', JUNK PIPE IN WELL BORE UNABLE TO RETRIEVE PIPE, SHOT CASING AT 540', PUMPED 17 SACKS CEMENT AND 2 SACKS GEL, PULLED CASING TO 150', PUMPED 40 SACKS. CEMENT TO SURFACE, PULLED CASING OUT.

RECEIVED
KCC DISTRICT #3

MAY 23 2006 *SL*

CHANUTE, KS

Perfs:

Remarks: GPS SPOT LOCATION

Plugged through:

INVOICE
DATE: 5-25-06
NO. 2006061716

District: 03

Signed Mike Heffern by SL
(TECHNICIAN)

RECEIVED
MAY 25 2006
KCC WICHITA

PLS