

To: 6 040983
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

12-7 15-163-03772-00-02
API NUMBER 15- 12-9-53

SEC. 9 T 8 S, R 17 W/E

TECHNICIAN'S PLUGGING REPORT

Operator License # 3846 Lease Name Krug Well # 9

Operator: Tom Rush
Name & Address: Box 322
County Rooks Rooks 124.41

Well Total Depth 3828 feet
Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 1305 w/600 sks

Abandoned Oil Well _____ Gas Well _____ Input Well SWD Well _____ U&A _____

Other well as hereinafter indicated _____ Supply Well _____

Plugging Contractor Allied Cementing License Number _____

Address Russell, Ks.

Company to plug at: Hour: 8:30AM Day: 7 Month: Dec Year: 19 88

Plugging proposal received from Dewey Gressell

(company name) Tom Rush (phone) _____

were: 5 1/2" casing set at 3482' w/175 sks. Tubing fish at 1690'. 4 1/2" liner

at 3389' - 3519' w/50 sks cement. Ordered 500 sks 65/35 Poz 10% Gel 2% Lite w/1/4# F.C. plus

12 sks Hulls, plus 40 sks gel.

Plugging Proposal Received by Dennis L. Hamel

(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 3:30PM Day: 7 Month: Dec Year: 19 88

ACTUAL PLUGGING REPORT Ran tubing to 1685'. Pumped 250 sks 65/35 Poz

10% Gel 2% Lite w/1/4# F.C. w/6 sks (no circ). Pulled to 1300'. Pumped 39 sks gel w/6 Hulls

cir gel to surface. Followed w/35 sks cement. Pulled tubing to 700'. Pumped 100 sks cement

w/2 Hulls, pulled tubing pumped add. 40 sks cement. Max 800# SI 200. Pumped in 8 5/8"

casing 75 sks cement w/1/4 F.C. plus 2 sks Hu-1s mixed in cement. Max 300# S.I. 200# psi.

Remarks: _____

(If additional description is necessary, use BACK of this form.)

(did / did not observe this plugging.)

INVOICED

DATE 1-20-89

INV. NO. 23718

Signed Dennis L. Hamel
(TECHNICIAN)
Dennis L. Hamel