

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-21287-00-00
Spot: CNWNENE Sec/Twnshp/Rge: 19-8S-17W
4950 feet from S Section Line, 990 feet from E Section Line
Lease/Unit Name: STAMPER Well Number: 3
County: ROOKS Total Vertical Depth: 3400 feet

Operator License No.: 31013 Conductor Pipe: Size feet: 9 1/2
Op Name: BROWN, DON DBA THE DON BROWN C Surface Casing: Size 8.625 feet: 167 100 SX CMT
Address: PO BOX 24 Production: Size 4.5 feet: 3399 150 SX CMT
PLAINVILLE, KS 67663 Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 11/26/2002 9:00 AM
Plug Co. License No.: 31013 Plug Co. Name: BROWN, DON DBA THE DON BROWN CO.
Proposal Rcvd. from: DON BROWN Company: BROWN, DON DBA THE DON BRO Phone: (785) 434-4944

Proposed Plugging Method: Ordered 225 sxs 60/40 pozmix - 10% gel - 500# hulls - 10 sxs gel.
W.L.M. to 3390'. Perfs 3244' - 3387'.
Casing squeeze at 1070' w/300 sxs cement.

Plugging Proposal Received By: DENNIS HAMEL Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 11/26/2002 11:00 AM KCC Agent: DENNIS HAMEL

Actual Plugging Report:

R.U. Cementers to 4 1/2" casing.
Squeezed 20 sxs cement with 300# hulls mixed in cement, followed with 10 sxs gel, followed with 155 sxs cement.
Max. P.S.I. 300#. S.I.P. 100#.
Rigged up cementers to 8 5/8" S.P.
Squeezed 25 sxs cement with 100# hulls.
Max. P.S.I. 300#. S.I.P. 100#.

DEC 11, 2002
KCC

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed Dennis J. Hamel
(TECHNICIAN)

INVOICED

Form CP-2/3

DATE 12-12-02

INV. NO. 2003060932

DEC 03 2002

THE GENE BROWN CO.
407 S. MAIN

REPLACEMENT CARD:

19-8-17W
NW NE NE

PLAINVILLE, KS. 67663
CONTR LAWBANCO DRILLING CO.

#3 STAMPER

CTY ROOKS

GEOL ERIC WADDELL

FIELD DOPITA

E 1913 KB CM 4/11/81 CARD ISSUED 8/6/81 IF P 6 B0 & 80 BWPD
1908 GL ARB 3356-3376

API 15-163-21,287

SMP	TOPS	DEPTH	DATUM
TOP		2834	- 921
HEEB		3043	-1130
TOR		3069	-1156
LKC		3088	-1175
B KC		3313	-1400
MARM		3318	-1405
SIMP		3341	-1428
ARB		335U	-1437
RTD		340U	-1487

8-5/8" 167/100sx, 4½" 3399/150sx

NO DST'S
MICT - CO, PF (ARB) 80/3356-76,
AC 5000 G (15% REG), SWB DWN W/GSO,
POP, P 6 B0 & 80 BWP, 6/8/81

INFO RELEASED: 10/8/81 - WAS OIL WELL
TIGHT HOLE

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS