

4-070125

12-1

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15-163-21,247 -00-00

SE NE NE /4 SEC. 19, 08 S, 17 W
4290 feet from S section line
330 feet from E section line

Operator license# 31013 Lease: Stamper Well # 2

Operator: The Don Brown Company County: Rooks 110.27

Address: P.O. Box 24 Well total depth 3393 feet
Plainville, Kansas 67663 Conductor Pipe: 0 inch @ 0 sxs.
Surface pipe 8 5/8 Inch @ 166 feet
W/100 sxs.

ABAND. oil well X, Gas well, Input well, SWD., D&A

Plugging contractor: Allied Cement Company License# -

Address: Russell, Kansas 67665

Company to plug at: Hour: 9:30 A.M. Day: 1 Month: December Year: 1998

Plugging proposal received from: Don Brown

Company: The Don Brown Company Phone: 785-434-4944

Were: 4 1/2" set at 3392' w/150 sxs. ARB.perfs. 3326' - 3352'. CIBP set at 3308'.
Ordered out 275 sxs - 60/40 pozmix - 10% gel - 800# hulls.
LKC perfs at 3216' - 3257'.
Emergency plug orders given while rig over the hole.
No Alt.2. Found shiny spot on tubing at 1620' salt section. F.L. 600'

1998 DEC - 7

Plugging Proposal Received by: Rich Williams

Plugging operations attended by agent? All [X], Part [], None []

Completed: Hour: 11:45 A.M. Day: 1, Month: December, Year: 1998

Actual plugging report: LK Wireline perforated 1250' Anhy and Dakota at 675'.
Shiny spot on tubing at 1620' salt section. Fluid level 600'.
Ran 2 3/8" tubing to 2000'. Allied pumped 100 sxs 60/40 pozmix with 10% gel and 400# hulls.
Pulled to 1293' and pumped 80 sxs cement with 300# hulls. Lost circulation - pulled to 677'.
Pumped 25 sxs cement - circulated. PTOH. Squeezed 20 sxs cement. Max. P.S.I. 400#. S.I.P. 100#.
Hooked-up backside and pumped 50 sxs 60/40 pozmix - 10% gel with 100# hulls.
Max. P.S.I. 400#. S.I.P. 100#.

Remarks:

Condition of casing(in hole): GOOD BAD X Anhy.plug: YES X NO
Bottom plug(in place): YES X, CALC, NO Dakota plug: YES X, NO
Plugged through TUBING X, CASING Elevation: 1886 GL

I did [X] / did not [] observe the plugging.

Richard Williams
(agent)

Form CP-2/3

100

DEC 16 1998

60447