

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-22186-00-00
Spot: CNWNENW Sec/Twnshp/Rge: 19-8S-17W
4950 feet from S Section Line, 3630 feet from E Section Line
Lease/Unit Name: SCHINDLER B Well Number: 4
County: ROOKS Total Vertical Depth: 3409 feet

Operator License No.: 31013 Conductor Pipe: Size _____ feet: 8/10.79
Op Name: BROWN, DON DBA THE DON BROWN C Surface Casing: Size 8.625 feet: 175 130 SX CMT
Address: PO BOX 24 Production: Size 5.5 feet: 3409 130 SX CMT
PLAINVILLE, KS 67663 Liner: Size _____ feet: _____

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/06/2002 10:00 AM
Plug Co. License No.: 31013 Plug Co. Name: BROWN, DON DBA THE DON BROWN CO.
Proposal Rcvd. from: DON BROWN Company: BROWN, DON DBA THE DON BRO Phone: (785) 434-4944

Proposed Plugging Method: Ordered 350 sxs 60/40 pozmix - 10% gel - 500# hulls.
Tubing fish at 1320'. Holes in the casing.

Plugging Proposal Received By: DENNIS HAMEL Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 08/06/2002 2:00 PM KCC Agent: DENNIS HAMEL

Actual Plugging Report:

Ran in hole with tubing to 1200' plus.
Spotted 250 sxs cement with 400# hulls to circulate at surface.
POOH with tubing and squeezed casing with 35 sxs additional cement.
Max. P.S.I. 400#. S.I.P. 400#.
Squeezed 8 5/8" S.P. with 25 sxs cement plus 100# hulls.
S.I.P. 200#.

RECEIVED
SEP 17 2002
SEP 17, 2002
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed Dennis L. Hamel
(TECHNICIAN)

INVOICED

Form CP-2/3

DATE 9-18-02
VV NO. 2003060520

SEP 12 2002

THE GENE BROWN COMPANY
407 S. MAIN

#4 "B" SCHINDLER

19-8-17W
NW NE NW

PLAINVILLE, KS 67663

CONTR DREILING OIL, INC.


CTY ROOKS

GEOL TONY KRUSE

FIELD DOPITA

ELV 1955 KB SPD 10/26/83 CARD ISSUED 2/24/84 IP P 12 BO & 6 BWPD
1950 GL. LKC 3234-3338 OA

API 15-163-22,186



LOG	Tops	Depth/Datum	
*ANH	1296+	659	8 5/8 " 175/130 SX; 5 1/2 " 3409/130 SX NO DST'S MCT - CO, PF (LKC) 3335-38, W/2 SPF, AC 1000 G (28%), SWB LD, SO, PF (LKC) 3313-18, 3294.99, W/2 SPF, AC 2000 G (28%), SWB LD, SO, PF (LKC) 3234-38, W/2 SPF, AC 1000 G (28%), SWB LD, SO, SET 2 3/8 " TBG AT 3390, POP, P 12 BO & 6 BWPD (GR 36°), 12/7/83
*B/ANH	1330+	625	
TOP	2883-	928	
HEEB	3094-	1139	
TOR	3114-	1159	
LANS	3136-	1181	
BKC	3364-	1409	
PBTD	3399-	1444	
RTD	3415-	1460	
DRILLERS TOPS			

COPYRIGHT 1983
INDEPENDENT OIL & GAS SERVICE, INC.
WICHITA, KANSAS

114010CE5