

4-060944

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

8-15

API Number: 15-163-21,290 -00-00

E2 SE SE /4 SEC. 19, 08 S, 17 W
660 feet from S section line
330 feet from E section line

Operator license# 31013

Lease Schindler Well # B-1

Operator: Don Brown Company

County: Rooks 112.77

Address: P.O. Box 24
Plainville, Kansas 67663

Well total depth 3470 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 160 feet

Aband. oil well X, Gas well, Input well, SWD, D & A

Plugging contractor: Co Tools License#

Address:

Company to plug at: Hour: 5:00 P.M. Day: 15 Month: August Year: 1996

Plugging proposal received from: Don Brown

Company: Don Brown Company Phone:

Were: Order 235 sxs 60/40 posmix - 10% gel - hulls and 1/4# flocele per sack.

Plug through tubing.

Working on well testing for holes in casing. Decided to D&A.

Emergency permission to plug with rig over hole.

1996 AUG 21
RECEIVED
KANSAS CORPORATION COMMISSION
AUG 21 11:59 AM '96

Plugging Proposal Received by: Herb Deines

Plugging operations attended by agent? All [], Part [], None [X]

Completed: Hour: 9:00 P.M. Day: 15, Month: August Year: 1996

Actual plugging report: 8 5/8" to 160' w/70 sxs. 4 1/2" to 3469' w/150 sxs. Holes in casing at 500' and up, 870' and 1900'. Pulled RBP used to test for holes in casing. Ran in with tubing to 2034' and pumped 100 sxs cement with 300# hulls. Pulled tubing to 1086' and pumped 50 sxs with 100# hulls. Pulled tubing to 500' and pumped 50 sxs cement with 100# hulls with cement to surface. Pulled tubing. Tied onto annulus and pumped 40 sxs cement and shut in. Tied onto production casing and pumped 10 sxs with 300# Max. P.S.I. S.I.P. 300#.


Remarks: Halliburton Cementing.

Condition of casing(in hole): GOOD BAD X Anhy.plug: YES X NO

Bottom plug(in place): YES, CALC X, NO Dakota plug: YES X, NO

Plugged through TUBING X, CASING. Elevation: 1971 GL

I did not observe the plugging.


(agent)

DW

Form CP-2/3

INVOICED

DATE AUG 27 1996

INV. NO. 46351