

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-22187-00-00
Spot: NENENW Sec/Twnshp/Rge: 19-8S-17W
330 feet from N Section Line, 2310 feet from W Section Line
Lease/Unit Name: SCHINDLER B Well Number: 5
County: ROOKS Total Vertical Depth: 3428 feet

Operator License No.: 31013
Op Name: BROWN, DON DBA THE DON BROWN C
Address: PO BOX 24
PLAINVILLE, KS 67663

Conductor Pipe: Size feet: 8 1/1.41
Surface Casing: Size 8.625 feet: 175 130 SX CMT
Production: Size 5.5 feet: 3398 130 SX CMT
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 11/26/2002 1:00 PM
Plug Co. License No.: 31013 Plug Co. Name: BROWN, DON DBA THE DON BROWN CO.
Proposal Rcvd. from: DON BROWN Company: BROWN, DON DBA THE DON BRO Phone: (785) 434-4944

Proposed Plugging Method: Ordered 225 sxs 60/40 pozmix - 10% gel - 500# hulls.
Bridge at 2225'.
Run tubing to 2200'+.

Plugging Proposal Received By: DENNIS HAMEL Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 11/26/2002 3:00 PM KCC Agent: DENNIS HAMEL

Actual Plugging Report:

R.I.H. with tubing to 2200'.
Spotted 200 sxs cement with 500# hulls - circulated at surface.
POOH with tubing. Rigged up to 5 1/2" casing and squeezed with 25 sxs cement.
Max. P.S.I. 300#. S.I.P. 100#.
Rigged up cementers to 8 5/8" S.P.
Squeezed 25 sxs cement with 100# hulls.
Max. P.S.I. 300#. S.I.P. 100#.

DEC 11 2002
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

102

Signed

Dennis L. Hamel

(TECHNICIAN)

INVOICED

Form CP-2/3

DATE

12-12-02

INV. NO.

2003060932

DEC 03 2002

THE GENE BROWN COMPANY
407 S. MAIN

#5 "B" SCHINDLER

19-8-17W
NE NE NW


PLAINVILLE, KS 67663

CONTR DREILING OIL, INC.

CTY ROOKS

GEOL

FIELD DOPITA



ELV 1965 KB SPD 10/21/83 CARD ISSUED 2/24/84 IP P 15 BO & 4 BWPD
1960 GL LKC 3237-3350 OA
API 15-163-22,187

LOG	Tops	Depth/Datum	
			8 5/8 " 175/130 SX; 5 1/2 " 3398/130 SX
			NO DST'S
			MICT - CO, PF (LKC) 3367-70, 3348-50, W/2 SPF, AC 2000 G
			(28%), SWB LD, SO, PF (LKC) 3326-31, 3310-15, AC 2000 G
			(28%), SWB LD, SO, PF (LKC) 3250-52, 3227-40, W/2 SPF, AC
			2000 G (28%), SWB LD, SO, SET 2 3/8 " TBG AT 3380, POP, P
			15 BO & 4 BWPD (GR 36.5°), 11/28/83
TOP	2894-	929	
HEEB	3106-	1141	
TOR	3127-	1162	
LANS	3148-	1183	
BKC	3377-	1412	
PBTD	3385-	1420	
RTD	3428-	1463	

COPYRIGHT 1983
INDEPENDENT OIL & GAS SERVICE, INC.
WICHITA, KANSAS