

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-095-22030-00-00
Spot: W2SWNW Sec/Twnshp/Rge: 35-28S-6W
1980 feet from N Section Line, 330 feet from W Section Line
Lease Name: SIMS TRUST Well #: 1-35
County: KINGMAN Total Vertical Depth: 4338 feet

Operator License No.: 5399
Op Name: AMERICAN ENERGIES CORPORATION
Address: 155 N. MARKET, STE 710
WICHITA, KS 67202

String Size Depth (ft) Pulled (ft) Comment
SURF 8.625 234

\$ 140.99

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 05/04/2006 8:00 AM
Plug Co. License No.: 5123 Plug Co. Name: PICKRELL DRILLING COMPANY, INC.
Proposal Rcvd. from: MIKE KERN Company: PICKRELL DRILLING COMPANY, I Phone: (316) 262-8427

Proposed Plugging Method: 35 sxs @ 800'; 35 sxs @ 400'; 35 sxs @ 284'; 25 sxs @ 60' to surf; and 15 sxs in rathole.

Plugging Proposal Received By: DUANE KRUEGER WitnessType: NONE
Date/Time Plugging Completed: 05/04/2006 10:00 AM KCC Agent: GREG EVES

RECEIVED
KCC DISTRICT #2
MAY 18 2006
WICHITA, KS

Actual Plugging Report:

Perfs:

Pumped 35 sacks of cement through drill pipe at 800'. Pumped 35 sacks of cement at 400'.
Pumped 35 sacks of cement at 284'. Pumped 25 sacks of cement at 60' and circulated to
surface. Pumped 15 sacks of cement in the rathole.

Allied #23132

145 sxs total of 60/40 posmix with 4% gel

Remarks:
Plugged through: DP

District: 02

Signed Greg Eves

(TECHNICIAN)

RECEIVED

JUN 01 2006

KCC WICHITA

Form CP-2/3

INVOICED
DATE 6-1-06
SERIAL 2006061734

M

PKT