

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-21267-00-01
Spot: NENWSE Sec/Twnshp/Rge: 31-12S-20W
2310 feet from S Section Line, 1650 feet from E Section Line
Lease Name: HUBER B Well #: 5
County: ELLIS Total Vertical Depth: 3980 feet

Operator License No.: 3134
Op Name: MORRIS, TERRY E. DBA G L M COMPA
Address: PO BOX 193
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3872	0	w/225 sxs cmt
SURF	8.625	198	0	w/150 sxs cmt

\$129.35

Well Type: SWD UIC Docket No: D20852.0 Date/Time to Plug: 05/24/2006 12:00 PM
Plug Co. License No.: 33674 Plug Co. Name: DAVE'S WELL SERVICE, LLC
Proposal Rcvd. from: DAN REINHARDT Company: DAVE'S WELL SERVICE, LLC Phone: (785) 483-7332

Proposed Plugging Method: Ordered 310 sxs cement and 500# hulls.

Plugging Proposal Received By: HERB DEINES WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 05/24/2006 4:00 PM KCC Agent: ROGER MOSES

Actual Plugging Report:

Perfs:

DV Tool at 1503' w/350 sxs.
Tubing fish in hole at 1736' - milled for several days on fish, entire time felt like mush.
Plastic liner - but no solid tubing.
Ran tubing to 1716' - circulated with 130 sxs cement with 500# hulls.
Pulled all tubing and squeezed 5 1/2" casing with 50 sxs cement.
Max. P.S.I. 1000#. S.I.P. 1000#.
Tied to 8 5/8" x 5 1/2" annulus and squeezed 15 sxs cement.
Max. P.S.I. 400#. S.I.P. 400#.
Total of 195 sxs 60/40 pozmix - 10% gel and 500# hulls.

INVOICED
DATE 6-1-06
INV. NO. 2006061736

Remarks: EVANS TANK-WATER.

Plugged through: TBG

District: 04

Signed Roger L. Moses
(TECHNICIAN)

RECEIVED

JUN 01 2006

KCC WICHITA

Form CP-2/3

MAY 30 2006

PKT

11/11/77

D-20,852

7

JERRY W. WILLIAMSON
 E12 BITTING BLDG.
 WICHITA, KS.
 CONTR H-30, INC.

#5 HUBER "B"

CTY ELLIS

FIELD ELLIS

AM 15-051-21,267

E 2163 KB CM 1/25/77 CARD ISSUED 4/21/77 IF P 25 BOPD N/W TOP 3194-99

31-12-20W
 NE NW SE

+	+	+
+	+	+
+	+	+

SMP	TOPS	DEPTH	DATUM
A^H		1514	+ 649
B ANH		1557	+ 606
TOP		3168	-1005
HEEB		3398	-1235
TOR		3418	-1255
LANS		3435	-1272
BKG		3689	-1526
MARM		3712	-1549
CONG		3761	-1598
ARB		3840	-1677
GRAN		3971	-1808
RTD		3980	-1817

8-5/8" 198/150sx, 5 1/2" 3872/225sx, OV
 1503/350sx
 DST (1) 3198-3204/30-30-30-30 90' OC
 W/FO, SIP 856-834# FP 32-43# 53- :#
 (2) 3730-3750/30-30-30-30, 420' G
 120' MOCW, 240' BLK WTR, SIP 1106-
 1096# FP 43-106# 138-191#
 DST (3) 3871-3980/30-30-30-30, 2731' G
 SIP 1263-1263# FP 960-1263# 1263-
 1263#
 MICT - CO TD, AC 1500, INJ. RATE SAT
 BP @ 3243, PF (TOP) 3194-99, AC 500, EC
 LD, RE-AC 1500, REC LD, SWB 6.7 BFPH.
 65% OIL, T&R, POP

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS