

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-153-20175-00-00  
Spot: SWNW Sec/Twnshp/Rge: 2-1S-34W  
3300 feet from S Section Line, 4620 feet from E Section Line  
Lease Name: OHLSON Well #: 7  
County: RAWLINS Total Vertical Depth: 4320 feet

Operator License No.: 30606  
Op Name: MURFIN DRILLING CO., INC.  
Address: 250 N. WATER, STE 300  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	4319	0	w/225 sxs cmt
SURF	8.625	277	0	w/225 sxs cmt

**\$ 140.40**

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/26/2006 10:00 AM  
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.  
Proposal Rcvd. from: JOHN TURNER Company: MURFIN DRILLING CO., INC. Phone: (785) 462-1031

Proposed Plugging Method: Ordered 300 sxs Midcon II Cement and 1000# hulls.  
Plug through tubing.

Plugging Proposal Received By: HERB DEINES Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 05/26/2006 1:30 PM KCC Agent: DARREL DIPMAN

**Actual Plugging Report:**

8 5/8" surface casing set at 277' w/225 sxs cement.  
5 1/2" production casing set at 4319' w/225 sxs cement.  
PBT 4280'. TD 4320'. Top of cement at 3092'.  
Ran tubing to 2500' - pumped 125 sxs cement with 500# hulls.  
Pulled tubing to 1250' - pumped 65 sxs cement with 200# hulls.  
Pulled tubing to 600' - pumped 60 sxs cement with 100# hulls - cement to surface.  
Pulled tubing to surface. Connected to 5 1/2" production casing - pumped 10 sxs cement.  
Max. P.S.I. 300#. S.I.P. 0#.  
Connected to 8 5/8" surface pipe - pumped 40 sxs cement.  
Max. P.S.I. 300#. S.I.P. 200#.

**Perfs:**

Top	Bot	Thru	Comments
4086	4274		

INVOICED

Remarks: LEASE RE-NAMED CAHOJ NE 'B' #1-7. SWIFT SERVICES, INC. #9132.

Plugged through: TBG

District: 04

Signed Darrel Dipman  
(TECHNICIAN)


RECEIVED  
JUN 01 2006  
KCC WICHITA

Form CP-2/3

MAY 30 2006

PVT

MURFIN DRILLING CO. #7 OWSON 2-1-34W  
 617 UNION CENTER, WICHITA, KS. C SW NW  
 CONTR CO. TOOLS CTY RAWLINS  
 GEOL \_\_\_\_\_ FIELD CAHOJ NE  
 E 3123 KB CM 1/12/74 CARD ISSUED 5/23/74 IP P 23 BOPD + 23 BWPD  
LANS 4132-38



API 15-153-20,175

LOG	TOPS	DEPTH	DATUM
ANH		2986	+ 137
TOP		3837	- 714
OREAD		3926	- 803
DOUG		3996	- 873
LKC		4033	- 910
BKC		4301	-1178
LTD		4313	-1190
RTD		4320	-1197

8-5/8" 277/225SX, 5 1/2" 4319/225SX  
 DST (1) 4049-4119/30-30-30-30, REC 50'M,  
 SIP 585-532#, FP 30-59#  
 DST (2) 4116-50/30-30-90-45, REC 90'M,  
 5' FO, SIP 245-384#, FP 31-74#  
 DST (3) 4148-4240/30-30-30-30, REC 10'  
 M, BHP 150-85#, FP 63-74#  
 DST (4) 4240-4320/30-30-30-30, REC 120'  
 M, SIP 1101-943#, FP 125-133#  
 MICT - PF 34/4132-38, 2000 ACID, REC  
 LD & SWB 18BF/3HRS, 50%W, FU 200' OIL  
 675' WTR, ON, POP

INDEPENDENT OIL & GAS SERVICE  
 WICHITA, KANSAS