

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-015-21375-00-00
Spot: S2SEW Sec/Twnshp/Rge: 11-28S-4E
3264 feet from S Section Line, 3388 feet from E Section Line
Lease Name: AUGUSTA UNIT Well #: 5-53
County: BUTLER Total Vertical Depth: 2599 feet

Operator License No.: 5030
Op Name: VESS OIL CORPORATION
Address: 8100 E. 22ND N. BLDG. 300
WICHITA, KS 67226

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		2490		
PROD	5.5	2588		250 SX
SURF	8.625	257		200 SX

\$ 84.47

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/19/2006 6:00 AM
Plug Co. License No.: 30437 Plug Co. Name: UNITED CEMENTING AND ACID CO., INC.
Proposal Rcvd. from: CASEY COATS Company: VESS OIL CORPORATION Phone: (316) 682-1537

Proposed Plugging Method: See actual report.

Plugging Proposal Received By: DUANE KRUEGER WitnessType: PARTIAL
Date/Time Plugging Completed: 05/19/2006 3:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH with tubing at 2050'. United spotted 50 sacks of class A with 2% cc. Tagged cement at 1680'. Shot 5-1/2" casing at 875' and 710'. POOH with 710' of 5-1/2" casing. RIH with tubing at 310'. United mixed and pumped 120 sacks of 60/40 posmix with 4% gel to surface.

United #7119 & 6967

Perfs:

Top	Bot	Thru	Comments
2588	2599		SIMPSON OH
2088	2108		
2075	2080		KC

RECEIVED
KCC DISTRICT #2
MAY 24 2006
WICHITA, KS

INDEXED

Remarks: SIMPSON OH 2588'-2599'; CIBP @ 2490'; KC PERFS 2075'-2080', 2088'-2108'

Plugged through: TBG

District: 02

Signed Duane Krueger
(TECHNICIAN)

RECEIVED
JUN 01 2006
KCC WICHITA

Form CP-2/3