

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-019-26557-00-00

Spot: NENESW

Sec/Twnshp/Rge: 30-33S-13E

2290 feet from S Section Line,

2990 feet from E Section Line

Lease Name: JBD-BRUEN

Well #: JBD 1

County: CHAUTAUQUA

Total Vertical Depth: 1458 feet

Operator License No.: 31302

Op Name: JONES & BUCK DEVELOPMENT

Address: PO BOX 68

SEDAN, KS 67361

| String | Size | Depth (ft) | Pulled (ft) | Comment |
|--------|------|------------|-------------|---------|
|--------|------|------------|-------------|---------|

|      |     |      |   |  |
|------|-----|------|---|--|
| PROD | 4.5 | 1458 | 0 |  |
|------|-----|------|---|--|

|      |       |    |  |  |
|------|-------|----|--|--|
| SURF | 8.625 | 40 |  |  |
|------|-------|----|--|--|

Well Type: GAS

UIC Docket No:

Date/Time to Plug: 08/18/2005 8:00 AM

Plug Co. License No.: 32884

Plug Co. Name: ELMORE'S INC.

Proposal Rcvd. from: JOHN ELMORE

Company: ELMORES, INC.

Phone: (620) 249-2519

Proposed Plugging Method: TO PUMP CEMENT & GEL FOR BOTTOM & TOP PLUGS.

Plugging Proposal Received By: RON ROWE

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 08/18/2005 5:00 PM

KCC Agent: RON ROWE

Actual Plugging Report:

BULLHEAD PUMPED 10 SACKS CEMENT & GEL SPACER, THEN PRESSURED TO 800# & SHUT-IN. THEN RAN 1" SPOOL HOSE INSIDE 4.5" CASING TO 350' & PUMPED/CIRCULATED CEMENT TO SURFACE. PULLED SPOOL HOSE & TOPPED-OFF WELL. USED TOTAL OF 45 SACKS CEMENT & 2 SACKS GEL.

Perfs:

| Top | Bot | Thru | Comments |
|-----|-----|------|----------|
| 830 | 848 |      |          |

Remarks: PLUGGED INACTIVE GAS WELL - OPERATOR LOST LEASE.

Plugged through: CSG

District: 03

Signed

(TECHNICIAN)

INVOICED

DATE Aug 29, 05  
INVOICE NO. 200606.0398

RECEIVED

AUG 29 2005

KCC WICHITA

Form CP-2/3