

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-167-22555-00-00  
Spot: W2NWNE Sec/Twnshp/Rge: 33-15S-13W  
4620 feet from S Section Line, 2310 feet from E Section Line  
Lease Name: BERRY Well #: 2  
County: RUSSELL Total Vertical Depth: 3341 feet

Operator License No.: 4419  
Op Name: BEAR PETROLEUM, INC.  
Address: PO BOX 438  
HAYSVILLE, KS 67060

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	7	3338	0	125 SX
SURF	10.75	457	0	250 SX

\$ 108.58

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/23/2006 10:30 AM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: Ordered 350 sxs cement and 500# hulls.

Plugging Proposal Received By: HERB DEINES Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 05/23/2006 4:30 PM KCC Agent: ROGER MOSES

Actual Plugging Report:

Sanded well bore to 3290' w/7 sxs cement.  
Cut 7" casing off at 1433' - pulled two joints - spotted 120 sxs cement with 500# hulls.  
Pulled 7" casing to 450' - spotted 50 sxs cement.  
Pulled 7" casing to 210' - circulated with 150 sxs cement.  
Pulled all 7" casing - cellar remained full of cement.  
Total of 327 sxs 60/40 pozmix - 10% gel and 500# hulls.

Perfs:

Top	Bot	Thru	Comments
3338	3341		

INVOICED  
DATE 6-5-06  
2006061745

Remarks: COPELAND ACID & CEMENTING. QUALITY WELL SERVICE-WATER.

Plugged through: CSG

District: 04

*MD*

Signed

Roger Moses  
(TECHNICIAN)

RECEIVED

JUN 02 2006

KCC WICHITA

Form CP-2/3

MAY 31 2006

PCT


137

DERRICK-AMERICAN OIL, INC.  
 225 N. MARKET, #330 #2 BERRY 33-15-13W  
 WICHITA, KS 67202 C W/2 NW NE

CONTR DUKE DRILLING CO. CITY RUSSELL

GEOLOGIST ROBERT B. THOMPSON FIELD TRAPP

ELV 1896 KB SPD 1/17/85 CARD ISSUED 3/28/85 IP P 20 BOPD  
1891 GL DRLG COMP 1/23/85 ARB OH 3338-3341



SMP	Tops	Depth/Datum
ANH	.....	859+1037
TOP	.....	2772- 876
HEEB	.....	3005-1109
TOR	.....	3022-1126
DOUG	.....	3036-1140
BR LM	.....	3079-1183
LANS	.....	3083-1187
BKC	.....	3327-1431
ARB	.....	3336-1440
RTD	.....	3341-1445

API 15-167-22,555

10 3/4 " 457/250SX, 7" 3338/125SX  
 NO CORES OR DST'S  
 MICT - CO, (ARB OH), SWB DWN, SO, NAT, SET 2 1/2 " TBG AT  
 3302, POP, P 20 BOPD, 3/9/85