

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-22563-00-00
Spot: S2SWNENE Sec/Twnshp/Rge: 33-15S-13W
4240 feet from S Section Line, 990 feet from E Section Line
Lease Name: BERRY Well #: 4
County: RUSSELL Total Vertical Depth: 3975 feet

Operator License No.: 4419
Op Name: BEAR PETROLEUM, INC.
Address: PO BOX 438
HAYSVILLE, KS 67060

| String | Size | Depth (ft) | Pulled (ft) | Comment |
|--------|-------|------------|-------------|---------|
| PROD | 7 | 3565 | 1050 | 125 SX |
| SURF | 10.75 | 468 | 0 | 250 SX |

\$ 127.19

Well Type: SWD UIC Docket No: D23895.0 Date/Time to Plug: 05/15/2006 11:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: JOE MAES Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: Ordered out 350 sxs 60/40 pozmix - 10% gel - 600# hulls.
Shot casing free at 1050'.
4 1/2" fiberglass parted at 1840' - left in the hole.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 05/25/2006 4:30 PM KCC Agent: JAY PFEIFER

Actual Plugging Report:

05/15/2006 - Witnessed by Case Morris.
Swaged onto 7" - mixed and pumped 100 sxs cement with 400# hulls - displaced to 1800'.
05/25/2006 - Witnessed by Jay Pfeifer.
Shot casing free at 1050'.
Pulled up to 1020' - mixed and pumped 120 sxs cement with 100# hulls.
Pulled up to 450' - spotted 50 sxs cement with 100# hulls.
Pulled up to 150' - circulated cement with 75 sxs.
POOH. Hole full of cement.

Perfs:

| Top | Bot | Thru | Comments |
|------|------|------|----------|
| 3565 | 3976 | | |

INVOICED

DATE 6-5-06
WEL. NO. 2006061745

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

AD-

Signed

(TECHNICIAN)

JUN 01 2006

PGT

DERRICK-AMERICAN OIL, INC. 33-15-13W
 225 N. MARKET, #330 #4 BERRY 50'S.
 WICHITA, KS 67202 C SW NE NE
 CONTR DUKE DRILLING CTY RUSSELL
 GEOL STEVE PARKER FIELD TRAPP
 ELY 1898 KB SPD 2/2/85 CARD ISSUED 4/4/85 IP SWDW
 1893 GL DRLG COMP 2/13/85 ARB OH 3565-3575

| | | | |
|---|--|--|---|
| | | | A |
| + | | | |
| + | | | |
| + | | | |

| Tops | Depth/Datum |
|-------------------|---|
| NO TOPS AVAILABLE | API 15-167-22,563 |
| RTD | 10 3/4 " 468 / 250SX, 7" 3565 / 125SX |
| 3975-2077 | NO CORES |
| | DST (1) 3144-84 (LKC) / 30-30-30-30, SB THRU-OUT, REC 2320' |
| | SW, W / SCUM OIL ON TOP OF TOOL, SIP 1082-1082#, FP 526- |
| | 867 / 925-1057 |
| | MICT - CO. (ARB OH), SWB DWN, NAT, SET 4 1/2 " 3422' |
| | SWDW - INJECTION RATE SATISFACTORY |

COPYRIGHT 1984
 INDEPENDENT OIL & GAS SERVICE, INC.
 WICHITA, KANSAS