

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-019-19318-00-01

Spot: SENWSW

Sec/Twnshp/Rge: 3-35S-12E

1440 feet from S Section Line, 4580 feet from E Section Line *PCT*

Lease Name: TURNER BIG *Big Turner* Well #: 15

County: CHAUTAUQUA Total Vertical Depth: 983 feet

Operator License No.: 33066

Op Name: PRAIRIE METHANE GAS PRODUCERS

Address: 399258 W 1330 DR., DEWEY, OK 74029
BARTLESVILLE, OK 74029

String	Size	Depth (ft)	Pulled (ft)	Comment
--------	------	------------	-------------	---------

L1	2	983	400	
----	---	-----	-----	--

PROD	6.625	701	0	
------	-------	-----	---	--

Well Type: EOR

UIC Docket No: E06132.1

Date/Time to Plug: 05/24/2006 8:00 AM

Plug Co. License No.: 33066

Plug Co. Name: PRAIRIE METHANE GAS PRODUCERS LLC

Proposal Rcvd. from: LARRY UNDERHILL

Company: PRAIRIE METHANE GAS PRODUC Phone: (918) 534-2322

Proposed
Plugging
Method:

TO SHOOT-OFF 2" AS DEEP AS POSSIBLE & PULL OUT; THEN PERFORATE 6.6250" CASING; THEN TO RUN 1" WORK-STRING TO BOTTOM/TD & PUMP/CIRCULATE CEMENT TO SURFACE.

Plugging Proposal Received By: LARRY MARCHANT

WitnessType: PARTIAL

Date/Time Plugging Completed: 05/24/2006 12:10 PM

KCC Agent: RON ROWE

Actual Plugging Report:

Perfs:

RAN 1" WORK-STRING INSIDE 2" TO 975' & PUMPED 40 SACKS CEMENT FOR BOTTOM PLUG. PULLED 1" & SHOT-OFF 2" @ 403' (TRIED DEEPER), & PULLED 2" OUT. PERFORATED 6.6250" AT 392'. RAN 1" WORK-STRING BACK INSIDE 6.6250" TO 400' & PUMPED/CIRCULATED CEMENT TO SURFACE, INSIDE & OUTSIDE 6.6250" CASING. PULLED 1" & TOPPED-OFF WELL. USED TOTAL OF 140 SACKS CEMENT.

RECEIVED
KCC DISTRICT #3

JUN - 1 2006 *RR*

CHANUTE, KS

RECEIVED
JUN 06 2006
KCC WICHITA

Remarks: PLUGGED ABANDONED INJECTION WELL THAT FAILED MIT ON 4/27/2006.

Plugged through: TBG

District: 03

Signed

[Signature]
(TECHNICIAN)

INVOICED
DATE June 06, 2006
2006061756

Form CP-2/3

PCT