

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-191-20173-00-00
Spot: SENE Sec/Twnshp/Rge: 26-32S-4W
3419 feet from S Section Line, 557 feet from E Section Line
Lease Name: COFFMAN Well #: 1
County: SUMNER Total Vertical Depth: 4356 feet

Operator License No.: 5039
Op Name: AGV CORP.
Address: 123 N. MAIN
ATTICA, KS 67009

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		3950		
PROD	4.5	4054	2060	90 SX
SURF	8.625	252		220 SX

\$ 141.57

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 04/28/2006 10:00 AM
Plug Co. License No.: 33093 Plug Co. Name: GENESIS WELL SERVICE, INC.
Proposal Rcvd. from: KENT ROBERTS Company: AGV CORP. Phone: (316) 215-1683

Proposed Plugging Method: CIBP above perforations and 2 sacks of cement. Recover pipe; 35 sacks of cement at 600'; perforations at 2984'-2990'; squeezed 100 sacks of cement at 2994'; and CIBP at 2940'.

Plugging Proposal Received By: STEVE VANGIESON Witness Type: PARTIAL
Date/Time Plugging Completed: 04/28/2006 11:15 AM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

The CIBP was set at 2950' and capped with 2 sacks of cement. The casing was recovered from 2060'. Casing was pulled to 600' and 35 sacks of cement was spotted. Casing was pulled to 324' and circulated cement to surface.
60/40 posmix with 4% gel
Allied Cementing

Perfs:


Top	Bot	Thru	Comments
3970	3978		
2984	2990		

RECEIVED
KCC DISTRICT #2
MAY 25 2006
WICHITA, KS

Remarks:
Plugged through: CSG

RECEIVED
JUN 05 2006
KCC WICHITA

District: 02

Signed 

(TECHNICIAN)

INVOICED
DATE 6-6-06
2006061752

PCT