

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-191-22404-00-00  
Spot: N2SENE Sec/Twnshp/Rge: 26-32S-4W  
3644 feet from S Section Line, 535 feet from E Section Line  
Lease Name: RAY Well #: 1  
County: SUMNER Total Vertical Depth: 2995 feet

Operator License No.: 5039

Op Name: AGV CORP.

Address: 123 N. MAIN  
ATTICA, KS 67009

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	2991	1634	125 SX
SURF	8.625	267		275 SX

\$ 97.34

Well Type: GAS

UIC Docket No:

Date/Time to Plug: 04/27/2006 10:00 AM

Plug Co. License No.: 33093

Plug Co. Name: GENESIS WELL SERVICE, INC.

Proposal Revd. from: KENT ROBERTS

Company: AGV CORP.

Phone: (316) 215-1683

Proposed Plugging Method: CIBP at 2940' and cap with 2 sacks of cement. Recover pipe. Pull to 600' and spot 35 sacks of cement. Pull casing to 320' and circulate cement to surface.

Plugging Proposal Received By: STEVE VANGIESON

Witness Type: PARTIAL

Date/Time Plugging Completed: 04/27/2006 11:30 AM

KCC Agent: STEVE VANGIESON

Actual Plugging Report:

A CIBP was set at 2940' and capped with 2 sacks of cement. The casing was recovered from 1636'. The casing was pulled to 603' and spotted 35 sacks of cement. The casing was pulled to 270' and cement was circulated to surface.

60/40 posmix with 4% gel

Allied Cementing

Perfs:

Top	Bot	Thru	Comments
2991	2995		OPEN HOLE COMP

RECEIVED  
KCC DISTRICT #2  
MAY 25 2006  
WICHITA, KS

RECEIVED

JUN 05 2006


KCC WICHITA

Remarks:

Plugged through: CSG

District: 02

Signed



(TECHNICIAN)

INVOICED

DATE 6-6-06  
INV. NO. 2006061752

Form CP-2/3

PPT