

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-095-00288-00-01
Spot: NWNWNW Sec/Twnshp/Rge: 3-29S-6W
4950 feet from S Section Line, 4950 feet from E Section Line
Lease Name: KOSTNER OWWO Well #: 1-3
County: KINGMAN Total Vertical Depth: 4232 feet

Operator License No.: 5399
Op Name: AMERICAN ENERGIES CORPORATION
Address: 155 N. MARKET, STE 710
WICHITA, KS 67202

String Size Depth (ft) Pulled (ft) Comment
SURF 8.625 163

\$ 137,54

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 05/18/2006 7:00 AM
Plug Co. License No.: 5123 Plug Co. Name: PICKRELL DRILLING COMPANY, INC.
Proposal Rcvd. from: MIKE KERNS Company: PICKRELL DRILLING COMPANY, I Phone: (620) 786-7133

Proposed Plugging Method: 35 sxs @ 1100'; 35 sxs @ 600'; 50 sxs @ 200'; 25 sxs @ 60'; and 15 sxs in rathole.

Plugging Proposal Received By: STEVE VANGIESON WitnessType: PARTIAL
Date/Time Plugging Completed: 05/18/2006 9:00 AM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

Perfs:

The drill pipe was ran open end to 1100' and spotted 35 sacks of cement. Pulled drill pipe to 600' and spotted 35 sacks of cement. Pulled drill pipe to 200' and spotted 50 sacks of cement. Pulled drill pipe to 60' and circulated 25 sacks of cement to surface. Circulated 15 sacks of cement in rathole.

60/40 posmix with 4% gel

Allied Cementing

RECEIVED
KCC DISTRICT #2
MAY 25 2006
WICHITA, KS

Remarks:

Plugged through: DP

RECEIVED
JUN 05 2006
KCC WICHITA

District: 02

Signed

(TECHNICIAN)

INVOICED
June 6, 06
2006061753

PET